

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
July 2014
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 35269
Name: CK Oil & Gas, LLC
Address 1: 906 E Trapp St
Address 2: _____
City: Herington State: KS Zip: 67449 + 8901
Contact Person: Charles Kremeier
Phone: (405) 202-3481
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
Arbuckle Depth to Top: 2976 Bottom: 2979 T.D. 3040
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 035-24293-00-00
Spot Description: _____
SW NE SW NW Sec. 5 Twp. 30 S. R. 4 East West
1,897 Feet from North / South Line of Section
710 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Cowley
Lease Name: Rock Well #: 1-5
Date Well Completed: 05/20/2008
The plugging proposal was approved on: 11/10/2016 (Date)
by: Jeff Klock (KCC District Agent's Name)
Plugging Commenced: 11/14/2016
Plugging Completed: 11/17/2016

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
			8.625	254	0
			5.5	3010	1425

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Set CIBP at 2930', spotted 2 sacks cement with bailer on plug, came up to 1425', shot casing, pulled casing, ran tubing to 317', pumped cement plug to surface.

KCC WICHITA
NOV 18 2016
RECEIVED

Plugging Contractor License #: 30483 Name: Kremeier, Les (deceased) Kremeier Prod
Address 1: 3183 US Hwy 56 Address 2: _____
City: Herington State: KS Zip: 67449 + _____
Phone: (785) 258-2321
Name of Party Responsible for Plugging Fees: CK Oil & Gas, LLC
State of Kansas County, Dickinson, ss.
Charles Kremeier Employee of Operator or Operator on above-described well
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Charles Kremeier

Handwritten signature and date
11-17-16

810 E 7TH
 PO Box 92
 EUREKA, KS 67045
 (620) 583-5561



Cement or Acid Field Report
 Ticket No. **3039**
 Foreman Steve Neal Gray m.
 Camp Eureka KS

15-035-24294

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State	
11-17-16	1207	Rock 1-5				Butler	KS	
Customer CK Oil + Gas LLC			Safety Meeting		Unit #	Driver	Unit #	Driver
Mailing Address 906 E. Tropp St.					104	Allen m		
City Herrington			State KS		113	STEVEN		
Zip Code 67449								

Job Type PTA Hole Depth 3040' Slurry Vol. _____ Tubing 2 7/8 315'
 Casing Depth 3010' Hole Size 7 7/8" Slurry Wt. _____ Drill Pipe _____
 Casing Size & Wt. 5 1/2" Cement Left in Casing _____ Water Gal/SK _____ Other _____
 Displacement _____ Displacement PSI _____ Bump Plug to _____ BPM _____

Remarks: Safety Meeting: Rig up to 2 7/8 Tubing. Break circulation w/ Fresh water.
Mix 135 sks 60/40 Pozmix cement w/ 4% Gel 315' to surface. Pull out tubing
top well off. Job complete Rig down

KCC WICHITA

Thank you

NOV 18 2016

RECEIVED

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C105-2	1	Pump Charge	500.00	500.00
C107		Mileage <u>N/C</u>	-	-
C303	133 sks	60/40 Pozmix Cement	12.75	1721.25
C206	460	Gel 4% <u></u>	180	92.00
C105-A	5.81	Tenmiko's Bulk Truck	N/C	345.00
			6.75%	
			Subtotal	2658.25
			Sales Tax	179.43
Authorization <u>Called by Chris Kraenciar Title Cu. Rep</u>			Total	2837.68

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.