

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE NAME Messenger "L"
 WELL NUMBER #2
1650 Ft. from S Section Line
330 Ft. from E Section Line
 SEC. 12 TWP. 30 SRGE. 9W (E) or (W)
 COUNTY Kingman
 Date Well Completed 8-10-59
 Plugging Commenced 11-23-94
 Plugging Completed 11-29-94

LEASE OPERATOR McCoy Petroleum Corporation
 ADDRESS 3017 N. Cypress - Wichita, KS 67226-4003
 PHONE (316) 636-2737 OPERATORS LICENSE NO. 5003

Character of Well Oil
 (Oil, Gas, O&A, SWD, Input, Water Supply Well)
 The plugging proposal was approved on _____ (date)
 by Steve Van Gieson (XCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Mississippian Depth to Top _____ Bottom _____ T.O. 4412'
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD


| Formation | Content | From | To | Size | Put In | Pulled out |
|-----------|---------|------|-------|--------|--------|------------|
| | | 0 | 252' | 9-5/8" | 252' | None |
| | | 0 | 4411' | 5-1/2" | 4411' | 2506' |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug was used, state the character of same and depth placed, - from _____ feet to _____ feet each set
Plug and abandon using 60/40 Poz, 4% gel. Set 1st plug @ 1373' w/35 sx; 2nd plug @ 836' w/ 35 sx; 3rd plug @ 301' w/90 sx and circulate to surface. Top off with 10 sx.

Name of Plugging Contractor Shawnee Well Service License No. 30346
 Address P. O. Box 781624, Wichita, KS 67278-1624
 NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: McCoy Petroleum Corporation
 STATE OF KANSAS COUNTY OF SEDGWICK, ss. 3-7-95

McCoy Petroleum Corporation (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) [Signature]
 (Address) 3017 N. Cypress
 Wichita, KS 67226



before me this 6th day of March, 19 95
Deborah Ann Paulus
 Notary Public
January 8, 1996