

15-095-10001-0000 LEASE NAME Messenger "L"

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER #3
_____ Ft. from S Section Line
_____ Ft. from E Section Line

LEASE OPERATOR McCoy Petroleum Corporation
ADDRESS 3017 N. Cypress
PHONE# (316) 636-2737 OPERATORS LICENSE NO. 5003

SEC. 12 TWP. 30S RGE. 9W (S or W)
COUNTY Kingman
Date Well Completed 12-12-59
Plugging Commenced 2-22-95
Plugging Completed 2-23-95

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on _____ (date)
by Steve VanGieson (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? _____

Producing Formation Mississippian Depth to Top 4246 Bottom 4274 T.D. 4338

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		0	261	8-5/8"	261'	None
		0	4337	5-1/2"	4337'	1754'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from _____ feet to _____ feet each set
Plugged and abandon using 60/40 Pozmix, 4%gel. Set 1st plug @ 1371' w/ 35 sks; 2nd plug set @ 817' w/35 sks; 3rd plug set @ 299' w/80 sks and circulate to surface. Top off with 25 sks.


(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Shawnee Well Service License No. 30346
Address P. O. Box 781624, Wichita, KS 67278

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: McCoy Petroleum Corporation
STATE OF KANSAS COUNTY OF SEDGWICK, ss.

McCoy Petroleum Corporation (Employee of Operator or (Operator) c
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts
statements, and matters herein contained and the log of the above-described well as filed
the same are true and correct, so help me God.

(Signature) John Roy McCoy
(Address) 3017 N. Cypress
Wichita, KS 67226



before me this 17th day of March, 19 95
Deborah Ann Paulus
Notary Public
January 8, 1996

RECEIVED
STATE CORPORATION COMMISSION
MAR 20 1995