

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 5-14-54

15-095-30135-0000

LEASE NAME Messenger "L"

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER 4

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 12 TWP. 30S RGE. 9 ~~W~~ or W

LEASE OPERATOR McCoy Petroleum Corporation

COUNTY Kingman

ADDRESS 3017 N. Cypress, Wichita, KS 67226

PHONE# (316) 636-2737 OPERATORS LICENSE NO. 5003

Date Well Completed 5-14-64

Character of Well Oil

Plugging Commenced 2-21-95

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 2-22-95

The plugging proposal was approved on (date)

by Steve VanGieson (KCC District Agent's Name)

Is ACO-1 filed? Yes If not, Is well log attached?

Producing Formation Mississippian Depth to Top 4279 Bottom 4332 T.D. 4379

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		0	214'	8-5/8"	214'	None
		0	4636'	4-1/2"	4636'	1867'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Plugged and abandon using 60/40 Pozmix. Set 1st plug @ 1351' w/ 35 sks; 2nd plug @ 835' w/ 35 sks; 3rd plug @ 252' w/ 82 sks and circulate to surface. Top off with 25 sks.
 Plugging complete 2-22-95

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Shawnee Well Service License No. 30346

Address 3017 N. Cypress, Wichita, KS 67226

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: McCoy Petroleum Corporation


STATE OF KANSAS COUNTY OF SEDGWICK, ss.

McCoy Petroleum Corporation (Employee of Operator) or Operator

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) John Roger McCoy

(Address) 3017 N. Cypress, Wichita, KS 67226



before me this 17th day of March, 19 95

Deborah Ann Paulus
 Notary Public

January 8, 1996