

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Kingman County. Sec. 19 Twp. 30S Rge. ~~28E~~ 9 (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines C NW SW NE

Lease Owner Gulf Oil Corporation

Lease Name Katharine Piehl Well No. 1

Office Address Box 661, Tulsa, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) Dry hole

Date well completed 9-25 19 56

Application for plugging filed 9-28 19 56

Application for plugging approved 10-1 19 56

Plugging commenced 10-10 19 56


Plugging completed 10-20 19 56

Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

NORTH



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well M. A. Rives

Producing formation Depth to top Bottom Total Depth of Well 4902 Feet

Show depth and thickness of all water, oil and gas formations. PETD 4504'

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				5-1/2"	4504	2781.90'
				8-5/8"	239	- 0 -

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled with sand to 420' and dumped 5 sacks cement. Filled with mud to 230'. Set rock bridge from 230' to 220'. Dumped 20 sacks cement. Filled with mud to 35' and placed 5' rock bridge. Dumped 10 sacks cement which filled into cellar.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Mr. L. L. Gray
Address Box 2233, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
R. B. Tillerson (employee of owner) or (owner/representative) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. B. Tillerson

Box 2233, Wichita, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 26th day of October, 19 56

My commission expires 2-4-59

Ray W. [Signature]
STATE CORPORATION COMMISSION Notary Public.

22-7377-S 4-49-10M


JRM:BJT
10-26-56

PLUGGING
FILE SEC. 19 T. 30 R. 9W
BOOK PAGE 113 LINE 33

OCT 30 1956
10-30-56
CONSERVATION DIVISION
Wichita, Kansas

KATHARINE PIEHL NO. 1

NW SW NE Section 19-30S-9W
Kingman County, Kansas
Gulf Oil Corporation



8-5/8" O. D. casing cemented at 240'
5-1/2" O. D. casing cemented at 4902'

Drilling commenced August 25, 1956
Drilling completed September 17, 1956

FROM	TO	FORMATION	REMARKS
0	120	Sand	
120	190	Red bed	
190	240	Sand & red bed	8-5/8" O. D. casing cemented with
240	475	Red bed	250 sacks cement at 240'
475	1220	Shale & shells	
1220	1250	Anhydrite	
1250	1650	Shale & shells	
1650	1950	Shale & lime	
1950	2045	Lime	
2045	2535	Lime & shale	
2535	2655	Shale & lime	
2655	2840	Shale	
2840	2945	Shale & lime	
2945	3040	Lime & shale	
3040	3155	Lime	
3155	3285	Lime & shale	
3285	3367	Lime	
3367	3604	Lime & shale	
3604	3708	Sand & shale	
3708	3793	Lime & shale	
3793	4065	Lime	
4065	4087	Cherty lime	
4087	4324	Lime	
4324	4418	Lime & shale	
4418	4440	Mississippi chert	Coring 4422' - 4440'
4440	4472	Mississippi	Coring 4441' - 4471'
4472	4548	Lime	
4548	4566	Lime & chert	
4566	4592	Shale	
4592	4692	Shale & lime	
4692	4731	Lime	
4731	4751	Hard lime	
4751	4769	Lime, shale & sand	
4769	4800	Sand	
4800	4831	Sand & shale	
4831	4870	Shale	
4870	4883	Cherty lime	
4883	4902	Shale & lime	5-1/2" O. D. casing cemented at 4902'

T. D. 4902'

PLUGGING
 FILE SEC 19 T 30 R 9W
 BOOK PAGE 103 LINE 33