

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Kingman SEC. 19 TWP. 30 RGE. 9 N/W
 Location as in quarters or footage from lines:
SE/NE/SE

Locate Well
 correctly on above
 Section Platt.

Lease Owner Petroleum, Inc.
 Lease Name Westerman "C" Well No. #3
 Office Address Box 1447 - Great Bend, Kansas 67530
 Character of Well (Completed as Oil, Gas or Dry Hole): Oil
 Date Well Completed _____
 Application for plugging filed _____
 Plugging commenced January 02, 1982
 Plugging completed January 11, 1982
 Reason for abandonment of well or producing formation
Depleted
 Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Maurice V. Leslie
 Producing formation _____ Depth to top _____ bottom _____ T.D. 4445'
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8"	280'	NONE
				5 1/2"	4444'	2814.69'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Dumped sand to 4350' and five (5) sacks cement.
 Shot pipe @ 3820'.
 Pulled seventy (70) joints 5 1/2" casing.
 Squeezed well with fifteen (15) sacks gel, six (6) sacks
 hulls, ten (10) sacks gel, one hundred fifty (150) sacks
 50/50 pozmix cement with 2% added gel and 3% calcium chloride.

RECEIVED
 STATE CORPORATION COMMISSION
 1-18-82
 JAN 18 1982
 CONSERVATION DIVISION
 Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
 Name of Plugging Contractor Rockhold Engineering, Inc.

STATE OF KANSAS COUNTY OF BARTON, ss.
James W. Rockhold (employee of owner) or (owner or operator) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

(Signature) James W. Rockhold
JAMES W. ROCKHOLD
 (Address)

Box 698 - Great Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 15th day of Jan, 1982.

Ruth Brack
 Notary Public.

My Commission expires:



DRILLER'S LOG

PETROLEUM, INC.
Westerman 'C' #3
C SE NE SE Sec. 19-30S-9W
Kingman Co., Ks.

Commenced: 6-13-81
Completed: 6-23-81

Surface Casing: 280' of 8-5/8"
cemented w/225 sx common, 2% gel,
3% cc

<u>FORMATION</u>	<u>DEPTH</u>
Surface Hole	0 - 282
Sand & Shale	282 - 1760
Shale	1760 - 2199
Shale & Lime	2199 - 3415
Lime	3415 - 3548
Lime & Shale	3548 - 3756
Lime	3756 - 3880
Lime & Shale	3880 - 4055
Shale & Lime	4055 - 4169
Lime & Shale	4169 - 4328
Lime	4328 - 4445 RTD

I do hereby certify that the foregoing statements are true and correct to the best of my knowledge and belief.

RECEIVED
 STATE CORPORATION COMMISSION
 D N B DRILLING, INC.
 DEC 3 1 1981
 CONSERVATION DIVISION
 Wichita, Kansas
 James L. Donelson, Jr.

STATE OF KANSAS: ss:

Subscribed and sworn to before me this 23rd day of June, 1981

Dorothy L. Schmidt
 Dorothy L. Schmidt, Notary Public

DOROTHY L. SCHMIDT
 STATE NOTARY PUBLIC
 Sedgwick County, Kansas
 My Appt. Exp. April 30, 1983