


15-095-30274-00-00

WELL PLUGGING RECORD

Give All Information Completely
Take Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Kingman County. Sec. 20 Twp. 30 Rge. (E) 9 (W)
Location as "NE/CNW/SE" or footage from lines C NW SE
Lease Owner PICKRELL DRILLING COMPANY
Lease Name Lattimore "B" Well No. 1
Office Address 705 4th Natl. Bank Bldg, Wichita 2, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed June 21, 1963
Application for plugging filed June 21, 1963
Application for plugging approved June 21, 1963
Plugging commenced June 21, 1963
Plugging completed June 21, 1963
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Fred Hampel
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4429 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	299'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Heavy mud to 240'. Set plug. Cemented with
20 sacks cement. Heavy mud to 40'. Set plug.
Cemented with 10 sacks cement to bottom of
cellar. Plugged rat hole with 2 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
JUN 27 1963

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor PICKRELL DRILLING COMPANY
Address 705 4th National Bank Building, Wichita, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK, ss.
C. W. SEBITS ~~XXXXXXXXXXXX~~ (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. W. Sebits
C. W. SEBITS
705 4th National Bank Bldg, Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 24th day of June, 19 63

My commission expires June 21, 1966 Maxine Blackman Notary Public.

ROTARY DRILLING LOG

COMPANY: PICKRELL DRILLING COMPANY
705 4th Natl Bank Building
Wichita, Kansas
LOCATION: Lattimore B #1, C NW SE 20-30-9W
Kingman County, Kansas

Rotary Drilling Commenced 6-10-63
Rotary Drilling Completed 6-21-63

CONTRACTOR: PICKRELL DRILLING COMPANY
Wichita, Kansas

CASING RECORD: (6 jts) 8 5/8" surface casing set at 299', cemented with 175 sacks cement. Circulated. Completed at 2:30 P.M., June 10, 1963. No oil string run. D & A.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

140	Sand	C. F. S.
228	Red Rock	4360
1380	Shale & Shells	4370
1690	Shale & Lime	4380
2170	Lime	4390
3330	Lime & Shale	4400
3389	Lime	4410
3635	Lime & Shale	4429
4213	Lime	
4352	Lime & Shale	<u>Slope Tests</u>
4429	Mississippian - RTD	2500
		3000
		3500
		4000
		<u>S. L. M.</u>
		3689
		4047
		4302

RECEIVED
STATE CORPORATION COMMISSION
JUN 27 1963
CONSERVATION DIVISION
Wichita, Kansas

The undersigned, C. W. SEBITS, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY
By [Signature]
C. W. SEBITS Attorney-in-Fact

STATE OF KANSAS
COUNTY OF SEDGWICK } ss.

On this 24th day of June, 1963, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. SEBITS, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.
My commission expires: June 21, 1966
[Signature]
Maxine Blackman Notary Public