


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

KINGMAN County. Sec. 20 Twp. 30 Rge. 9 (X) W (W)  
Location as "NE/CNW/SW" or footage from lines. SW SW NW



Locate well correctly on above  
Section Plat

Lease Owner PETROLEUM, INC.  
Lease Name LATTIMORE Well No. 1  
Office Address Route 2, Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed September 22, 1957  
Application for plugging filed September 23, 1957  
Application for plugging approved September 22, 1957  
Plugging commenced September 22, 1957  
Plugging completed September 22, 1957  
Reason for abandonment of well or producing formation No producible zone

If a producing well is abandoned, date of last production None 19\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M.A. Rives Box 8, Pratt, Kansas  
Producing formation ----- Depth to top ----- Bottom ----- Total Depth of Well 4480 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	237'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Mud up with heavy mud to 225' followed by wooden plug. Placed 15 sacks cement through drill pipe on to plug. Mud up to 25' followed by wooden plug and 5 sacks cement to base of well cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Garvey Drilling Company  
Address Route 2, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.  
Don Searle (employee of owner) or (~~owner~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.  
(Signature) Don Searle  
Route 2, Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 26th day of September 19 57  
Ed T. Brown  
Notary Public.

My commission expires July 11, 1960

PLUGGING  
FILE SEC 20 T. 30 R. 9W  
BOOK PAGE 48 LINE 14

9-27-57  
CONSERVATION DIVISION  
Wichita, Kansas

# WELL LOG

15-095-01306-0000

COMPANY PETROLEUM, INCORPORATED

SEC. 20 T. 30S R. 9W

FARM LATTIMORE NO. 1


LOC. SW, SW, NW

TOTAL DEPTH 4486'

COUNTY Kingman Co., Kansas

COMM. September 7, 1957 COMP. September 21, 1957

CONTRACTOR GARVEY DRILLING COMPANY



CASING 8 5/8" @ 237' W/225 sax.

ELEVATION 1710' DF

PRODUCTION D & A

FIGURES INDICATE BOTTOM OF FORMATIONS

130	Sand
160	Shale
238	Red bed & shale
950	Shale & shells
1450	Shale
1993	Lime & shale
2120	Lime
2638	Shale & lime
2787	Shale
3536	Shale & lime
3625	Sand, shale & lime
3710	Sand & shale
4199	Lime
4385	Lime & shale
4425	Chert
4486	Lime & shale
4486	T. D.

State of KANSAS }  
County of BARTON } ss:

**PLUGGING**  
FILE SEC. 20 T. 30 R. 9W  
BOOK PAGE 48 LINE 14 C.

STATE OF KANSAS COMMISSION

SEP 27 1957

CONSERVATION DIVISION  
Kansas

I, Verne A. Morris of Garvey Drilling Co.

upon oath state that the above and foregoing is a true and correct copy of the log of the #1 Lattimore well

Verne A. Morris

Subscribed and sworn to before me this 25th day of September 19 57

My Commission Expires: July 11, 1960

Edw. Brown  
NOTARY PUBLIC