

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

Kingman County. Sec. 20 Twp. 30S Rge. (E) 9 (W)

Location as "NE/CNW/SW" or footage from lines E/2 NW SW  
Lease Owner Monarch Oil and Gas Company  
Lease Name LAUTERBACH Well No. 1  
Office Address 1429 Wichita Plaza, Wichita, Kansas 67202  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed June 24, 19 68  
Application for plugging filed 19  
Application for plugging approved 19  
Plugging commenced June 24, 19 68  
Plugging completed June 24, 19 68  
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes (O. Warren)

Name of Conservation Agent who supervised plugging of this well  
Producing formation Depth to top Bottom Total Depth of Well 4442 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface	0	233'	8-5/8"	6/14/68	-----
	Casing					

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 27 1968  
CONSERVATION DIVISION  
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy Mud from Total Depth to 230 Feet;  
1/2 sax Hulls, Plug and 25 sax Cement thru  
the Drill Pipe; Mud to 40 Feet; 1/4 sax  
Hulls and Plug bridged with Kelley and  
8 sax to Base of Cellar; 2 sax in Rat Hole.  
Job completed at 2:30 A.M. 6/24/68.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sage Drilling Co., Inc.  
Address 500 Bitting Building, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Wayne W. Kahmeyer of Sage Drilling (employee of owner) or (owner or operator) of the above-described well being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wayne W. Kahmeyer  
500 Bitting Building, Wichita, Kansas



Subscribed and sworn to before me this 26th day of June 19 68

Louise K. Whitted  
Notary Public.

My commission expires November 26, 1970.

DRILLERS LOGLAUTERBACH NO. 1

CASING RECORD:	OPERATOR: Monarch Oil & Gas Co.	DESCRIPTION:
8-5/8" @ 233' w/200 sax cement	CONTRACTOR: Sage Drilling Co.	E/2 NW SW Sec. 20-30S-9W Kingman County, Kansas
TOTAL DEPTH: 4442'	COMMENCED: June 14, 1968	ELEVATION: 1704KB
	COMPLETED: June 24, 1968	

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Soil & Sand	0	90	
Sand & Red Bed	90	235	
Shale	235	375	
Shale & Shells	375	1485	
Shale & Lime	1485	1830	
Lime & Shale	1830	2706	
Shale & Lime	2706	2979	
Lime & Shale	2979	3510	
Shale & Lime	3510	3854	
Lime & Shale	3854	3910	
Lime	3910	4050	
Lime & Shale	4050	4300	
Lime & Chert	4300	4442	D&A


RECEIVED  
STATE CORPORATION COMMISSION  
JUN 27 1968  
CONSERVATION DIVISION  
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SAGE DRILLING CO., INC.

By Wayne W. Kahmeyer  
Wayne W. Kahmeyer

Subscribed and sworn to before me this 26th day of June, 1968.



Louise K. Whitted  
Louise K. Whitted - Notary Public

My commission expires:  
November 26, 1970.