

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-25780-00-00
Spot: E2NWSWSE Sec/Twnshp/Rge: 3-16S-14W
990 feet from S Section Line, 2040 feet from E Section Line
Lease Name: STEINLE Well #: 1
County: BARTON Total Vertical Depth: 3325 feet

Operator License No.: 33813
Op Name: JASON OIL COMPANY, LLC
Address: 3718- 183RD ST PO BOX 701
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3445	1600	150 SX
SURF	8.625	431		200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/11/2016 12:00 AM
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING
Proposal Rcvd. from: SHELDON WEIGEL Company: JASON OIL COMPANY Phone: (785) 483-4204

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement.

Plugging Proposal Received By: BRUCE RODIE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/11/2016 12:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perfs:

Sanded off perforations and topped with 5 sx cement. Cut casing at 1600'. Pulled casing to 1440' and pumped 125 sx cement w/200 # hulls. Pulled casing to 900' and pumped 50 sx cement w/100 # hulls. Pulled casing to 600' and pumped 50 sx cement w/100 # hulls. Pulled casing to 300'. Circulated cement to surface with 75 sx cement. Pulled casing and hole stayed full.

GPS: 38.68396 -098.85670

Remarks: QUALITY OILWELL CEMENTING

Plugged through: CSG

District: 04

Signed

Bruce Rodie

(TECHNICIAN)

cm

KCC WICHITA

OCT 31 2016

RECEIVED

NOV 21 2016

no

Form CP-2/3

OCT 17 2016