

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-167-06606-00-00
Spot: SWNW Sec/Twnshp/Rge: 31-12S-15W
3300 feet from S Section Line, 4620 feet from E Section Line
Lease Name: J BRUNGARDT Well #: 1
County: RUSSELL Total Vertical Depth: 3307 feet

Operator License No.: 6127

Op Name: KORON INVESTMENTS, INC.

Address: PO BOX 981
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3298		150 sx
SURF	8.625	963		350 sx

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 10/04/2016 11:00 AM

Plug Co. License No.: 6426

Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC

Proposal Rcvd. from: TERRY PIESKER

Company: KORON INVESTMENT, INC.

Phone: (785) 735-4363

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: RAY DINKEL

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 10/04/2016 2:00 PM

KCC Agent: RAY DINKEL

Actual Plugging Report:

Perfs:

Perforated at 350'. Well had holes at 1700' and 900'. Was squeezed with 400 sx cement early drilled out. Still leaking. Hole full of mud.
Ran tubing to 3050' and pumped 100 sx cement w/300 # hulls. Pulled tubing to 2070' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 1000' and pumped 125 sx cement. Circulated cement to pit. POOH. Hooked to casing and pumped 40 sx cement. Circulated cement out of braden head. Shut in pressure 250 - 300 psi.

GPS: 38.96712 -099.03679

Remarks: GLOBAL WELL SERVICES TICKET # 2751

Plugged through: TBG

District: 04

Signed

Ray A Dinkel

(TECHNICIAN)

cm

KCC WICHITA

OCT 31 2016

RECEIVED

NOV 21 2016

710

Form CP-2/3

OCT 10 2016