

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-24032-00-00
Spot: E2W2SE Sec/Twnshp/Rge: 36-18S-11W
1320 feet from S Section Line, 1650 feet from E Section Line
Lease Name: DOLL/MARY IDA Well #: 28
County: BARTON Total Vertical Depth: 3338 feet

Operator License No.: 30525
Op Name: LANGSTON, D. S.
Address: 310 W CENTRAL STE 202
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3336	1530	200 SX
SURF	8	302		250 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/13/2016 8:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: D.S. LANGSTON Company: D.S. LANGSTON Phone: (620) 786-0874

Proposed Plugging Method: Ordered 350 sx 60/30 pozmix 4% gel cement w/400 # hulls.

Plugging Proposal Received By: BRUCE RODIE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/13/2016 2:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report: _____ Perfs: _____

Sanded off perforations and topped off with 5 sx cement. Cut casing at 1530'. Pulled casing to 1300' and pumped 125 sx cement w/200 # hulls. Pulled casing to 800' and pumped 50 sx cement w/100 # hulls. Pulled casing to 550' and pumped 40 sx cement w/100 # hulls. Pulled casing to 250'. Circulated cement to surface with 50 sx cement. Pulled casing and hole stayed full.
GPS: 38.43816 -098.48635

Remarks: COPELAND ACID AND CEMENTING
Plugged through: CSG

District: 04 Signed Bruce Rodie (TECHNICIAN) CM
KCC WICHITA
OCT 31 2016 RECEIVED
OCT 17 2016
NOV 21 2016
Form CP-2/3