

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-051-26842-00-00
Spot: SENWNWNE Sec/Twnshp/Rge: 21-11S-16W
561 feet from N Section Line, 2005 feet from E Section Line
Lease Name: COMEAU Well #: 1-21
County: ELLIS Total Vertical Depth: 3420 feet

Operator License No.: 31385

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	939		350 SX

Op Name: M G OIL INC

Address: PO BOX 162
RUSSELL, KS 67665

Well Type: DH

UIC Docket No:

Date/Time to Plug: 08/28/2016 12:00 AM

Plug Co. License No.: 33905

Plug Co. Name: ROYAL DRILLING INC

Proposal Rcvd. from: DOUG

Company: ROYAL DRILLING INC

Phone: (785) 735-4142

Proposed
Plugging
Method:

Ordered 235 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: CASE MORRIS

WitnessType: NONE

Date/Time Plugging Completed: 08/28/2016 10:45 AM

KCC Agent: CASE MORRIS

Actual Plugging Report:

Perfs:

1st plug @3360 w/50 sx
2nd plug @975 w/100 sx
3rd plug @450 w/50 sx
4th plug @40 w/10 sx

Rathole 30 sx Mousehole 15 sx

Remarks: QUALITY

Plugged through: DP

District: 04

Signed



KCC WICHITA

(TECHNICIAN)

OCT 31 2016

RECEIVED

NOV 21 2016
MD

Form CP-2/3