

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-023-20691-00-00  
Spot: S2N2NWSE Sec/Twnshp/Rge: 15-2S-42W  
2200 feet from S Section Line, 1980 feet from E Section Line  
Lease Name: NORTHRUP Well #: 1-15  
County: CHEYENNE Total Vertical Depth: 1785 feet

Operator License No.: 9152  
Op Name: MAREXCO, INC.  
Address: PO BOX 21598  
OKLAHOMA CITY, OK 73156

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1774		75 SX
SURF	7	358		120 SX

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/04/2016 1:00 PM  
Plug Co. License No.: 34787 Plug Co. Name: GREEN OIL FIELD SERVICES, LLC  
Proposal Rcvd. from: STEPHEN MARDEN Company: MAREXCO Phone: (405) 286-5657

Proposed Plugging Method: Ordered 250 sx 60/40 pozmix 4% gel cement w/400 # hulls.  
7" surface casing set at 358' w/120 sx cement.  
4 1/2" production casing set at 1774' w/75 sx cement.  
TD 1785'.  
Perforations: 1668' - 1700'.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 10/04/2016 3:30 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

TIH with tubing to 1620' and pumped 55 sx cement w/200 # hulls. TOOH with tubing to 850' and pumped 70 sx cement w/50 # hulls. Cement circulated to surface. TOOH with tubing to surface. Connected to 4 1/2" production casing and pumped 10 sx cement. Connected to 7" surface casing and pumped 20 sx cement. Pressured to 300 psi.

GPS: 39.87850N -102.01870W

Perfs:

Top	Bot	Thru	Comments
1668	1700		

Remarks: GREEN OILFIELD SERVICES LLC PULLING UNIT AND CONSOLIDATED OILWELL SERVICES CEMENT TICKET # 51,584

Plugged through: TBG

District: 04

KCC WICHITA

OCT 31 2016

RECEIVED

*Darrel Dipman*

(TECHNICIAN)

NOV 21 2016

CM

OCT 10 2016

Form CP-2/3