

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-065-23726-00-00
Spot: W2NENENE Sec/Twnshp/Rge: 34-10S-24W
330 feet from N Section Line, 500 feet from E Section Line
Lease Name: GEYER Well #: 1-34
County: GRAHAM Total Vertical Depth: 4053 feet

Operator License No.: 31160
Op Name: PHILLIPS EXPLORATION COMPANY L.
Address: 211 CEDAR RIDGE CT PO BOX 850
ANDOVER, KS 67002

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4052		165 SX
SURF	8.875	220		150 SX
T1	2.875	3940		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/11/2016 9:00 AM
Plug Co. License No.: 32332 Plug Co. Name: FISCHER WELL SERVICE, INC.
Proposal Rcvd. from: JAMES B. PHILLIPS Company: PHILLIPS EXPLORATION COMPAN Phone: (316) 636-2256

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement, 12 sx gel and 400 # hulls.
Port Collar at 2020' w/400 sx cement.
Perforations: 3841' - 3843'.

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/11/2016 11:45 AM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3826' and pumped 12 sx gel followed by 50 sx cement w/200 # hulls. Pulled tubing to 2073' and pumped 100 sx cement w/100 # hulls. Pulled tubing to 1060' and pumped 125 sx cement. Good circulation of cement. Pulled tubing out and topped off casing with 25 sx cement. Tied on to backside and squeezed with 5 sx cement. Shut in pressure 300 psi.

GPS: 39.14564 -099.97943

Perfs:

Top	Bot	Thru	Comments
3841	3843		

Remarks: QUALITY CEMENT TICKET # 1799

Plugged through: TBG

District: 04

Signed _____

KCC WICHITA

OCT 31 2016

RECEIVED

(TECHNICIAN)

NOV 21 2016

no

CM

Form CP-2/3