

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-023-21239-00-00
Spot: NESWSWNE Sec/Twnshp/Rge: 15-4S-40W
2243 feet from N Section Line, 2264 feet from E Section Line
Lease Name: UPLINGER Well #: 32-15
County: CHEYENNE Total Vertical Depth: 1530 feet

Operator License No.: 33019
Op Name: ROSEWOOD RESOURCES, INC.
Address: 2101 CEDAR SPRINGS RD, STE 1500
DALLAS, TX 75201

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1509		60 SX
SURF	7	312		80 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 10/11/2016 12:00 PM
Plug Co. License No.: 8273 Plug Co. Name: EXCELL SERVICES, LLC
Proposal Rcvd. from: JAMES KREHMEYER Company: ROSEWOOD RESOURCES Phone: (970) 630-3880

Proposed Plugging Method: Ordered 150 sx 60/40 pozmix 4% gel cement w/150 # hulls.
7" surface casing set at 312' w/80 sx cement.
4 1/2" production casing set at 1509' w/60 sx cement.
TD 1530'. PBTB 1470'.
Perforations: 1306' - 1336'.
Top down plug.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/11/2016 2:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Connected to 4 1/2" production casing and pumped 90 sx cement w/150 # hulls. Pressured to 500 psi. Connected to 7" surface casing and pumped 30 sx cement. Pressured to 450 psi.
GPS: 39.70695 -101.79529W

Perfs:

Top	Bot	Thru	Comments
1306	1336		

Remarks: CONSOLIDATED OILWELL SERVICES TICKET # 51,625

Plugged through: CSG

District: 04

Signed Darrel Dipman
(TECHNICIAN)

KCC WICHITA
OCT 31 2016
RECEIVED

NOV 21 2016
no

Form CP-2/3