

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-065-23255-00-01
Spot: SESWSENE Sec/Twnshp/Rge: 8-9S-22W
2400 feet from N Section Line, 750 feet from E Section Line
Lease Name: VESPER BRANDYBERRY Well #: 1
County: GRAHAM Total Vertical Depth: 4015 feet

Operator License No.: 4767
Op Name: RITCHIE EXPLORATION, INC.
Address: 8100 E 22ND ST N # 700 BOX 783188
WICHITA, KS 67278

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| PROD | 4.5 | 4005 | | 175 SX |
| SURF | 8.625 | 237 | | 160 SX |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/13/2016 10:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: TOMMY ATKINS Company: RITCHIE EXPLORATION Phone: (785) 216-0155

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/500 # hulls.
Port Collar at 1814' w/300 sx cement.
Perforations: 3603' - 3607', 3619' - 3622', 3647' - 3650', 3702' - 3706', 3726' - 3729', 3740' - 3744', 3959' - 3963'.
CIBP at 3901'.

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/13/2016 12:45 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3820' and pumped 75 sx cement w/200 # hulls. Pulled tubing to 2820' and pumped 75 sx cement w/100 # hulls. Pulled tubing to 1920' and pumped 75 sx cement w/100 # hulls. Pulled tubing to 950' and pumped 70 sx cement. Good circulation of cement. Pulled tubing. Topped off casing with 15 sx cement. Visually checked backside and cement was to surface.

GPS: 39.28566 -099.79379

Perfs:


| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 3959 | 3963 | | |
| 3702 | 3744 | | |
| 3605 | 3650 | | |
| 3604 | 3607 | | |

Remarks: GLOBAL CEMENT TICKET # 2754

Plugged through: TBG

District: 04

Signed _____


(TECHNICIAN)

CM

KCC WICHITA

NOV 21 2016
no

Form CP-2/3

OCT 17 2016

OCT 31 2016

RECEIVED