

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-065-22708-00-00
Spot: E2NESW Sec/Twnshp/Rge: 9-10S-24W
1980 feet from S Section Line, 2310 feet from W Section Line
Lease Name: ANTON HERMAN Well #: 5
County: GRAHAM Total Vertical Depth: 4100 feet

Operator License No.: 6037
Op Name: STAAB OIL CO., A GENERAL PARTNER
Address: 1607 HOPEWELL RD
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4164		225 sx
SURF	8.625	225		150 sx

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/06/2016 8:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: TONY HERMAN Company: STAAB OIL CO. Phone: (785) 735-9405

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/300 # hulls.
Port Collar at 2175' w/150 sx cement.
Rods and tubing stuck in hole at 3100'.
Perforations: 4020' - 4028'.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/06/2016 11:45 AM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3000' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 2500' and pumped 100 sx cement. Pulled tubing to 1500' and pumped 105 sx cement. Good circulation of cement. Pulled tubing out and topped off with 20 sx cement. Tied on to backside and squeezed with 15 sx cement. Shut in pressure 300 psi.

GPS: 39.19431 -100.00714

Perfs:

Remarks: GLOBAL CEMENT TICKET # 2709

Plugged through: TBG

District: 04

KCC WICHITA

OCT 31 2016

RECEIVED

[Signature]

(TECHNICIAN)

C.M

OCT 18 2016

NOV 21 2016
20

Form CP-2/3