

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-101-21845-00-00
Spot: E2SWSW Sec/Twnshp/Rge: 18-16S-27W
762 feet from S Section Line, 4266 feet from E Section Line
Lease Name: DEBBIE Well #: 2
County: LANE Total Vertical Depth: 4595 feet

Operator License No.: 6569
Op Name: CARMEN SCHMITT, INC.
Address: PO BOX 47
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PC	5.5	2174		WITH 235 SX CMT
PROD	5.5	4573	0	WITH 200 SX CMT
SURF	8.625	218		WITH 150 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/20/2016 9:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: CURTIS HITCHMAN Company: CARMEN SCHMITT Phone: (620) 793-5100

Proposed Plugging Method: CIBP @ 4300' WITH 2 SX CMT OR 50 SX CMT WITH 250-300# HULLS. FILL WITH CMT FROM 2200' TO 0'. FILL ANNULUS WITH CMT.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/20/2016 1:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

RUN TBG TO 4255' & SPOTTED 100 SX CMT PLUG WITH 400# HULLS. PULL TBG TO 2405' & WAIT 1 1/2 HOURS. CIRCULATE CMT FROM 2405' TO SURFACE WITH 250 SX CMT. TOP OFF WITH 10 SX CMT. PUMP 20 SX CMT DOWN THE ANNULUS.

Perfs:


Top	Bot	Thru	Comments
4347	4355		

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

Signed



(TECHNICIAN)

RECEIVED
OCT 31 2016
KCC DODGE CITY

NOV 21 2016

Form CP-2/3

no