

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-129-10569-00-00  
Spot: SESW Sec/Twnshp/Rge: 35-34S-42W  
658 feet from S Section Line, 3311 feet from E Section Line  
Lease Name: WATSON Well #: 2-35  
County: MORTON Total Vertical Depth: 4224 feet

Operator License No.: 31345  
Op Name: THREE-D RESOURCES, INC.  
Address: PO BOX 856  
LIBERAL, KS 67905

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4140		WITH 2 SX CMT
PROD	5.5	4623	1710	WITH 400 SX CMT
SURF	8.625	1482		WITH 800 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/06/2016 9:00 AM  
Plug Co. License No.: 34199 Plug Co. Name: RAWHIDE WELL SERVICE, LLC  
Proposal Rcvd. from: KEITH CLUMSKY Company: THREE-D RESOURCES Phone: (620) 482-4647

Proposed Plugging Method: SET CIBP @ 4140' WITH 2 SX CMT. PERFORATE AT 1510' WITH 50 SX CMT 200# HULLS IN LAST 25 SX CMT. PERFORATE AT 400' WITH CMT TO 0'.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 10/06/2016 3:00 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

Perfs:

SET CIBP @ 4140' WITH 2 SX CMT. 1ST PLUG AT 1504' WITH 70 SX CMT. NO CIRCULATION. WAIT & TAGGED TOC @ 986'. 2ND PLUG AT 384' WITH 40 SX CMT. 3RD PLUG AT 64' WITH 20 SX CMT.

Top	Bot	Thru	Comments
4188	4205		

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA SI 10 YRS\*\* USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: TBG

District: 01

RECEIVED  
NOV 17 2016  
KCC DODGE CITY

Signed Kenny M Sullivan  
(TECHNICIAN)

NOV 21 2016 Form CP-2/3

*no*

*KMS*