

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-185-23891-01-00  
Spot: S2S2SESE Sec/Twnshp/Rge: 11-25S-11W  
159 feet from S Section Line, 653 feet from E Section Line  
Lease Name: EUBANKS Well #: 11 #1H  
County: STAFFORD Total Vertical Depth: 3850 feet

Operator License No.: 33596  
Op Name: UNIT PETROLEUM COMPANY  
Address: 8200 SOUTH UNIT DRIVE  
TULSA, OK 74132

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3650		WITH 5 SX CMT
COND 20		69		
II	9.625	1510		WITH 605 SX CMT
LI	5.5	8320	1600	WITH 400 SX CMT
PROD 7		4262	0	WITH 160 SX CMT
SURF	13.375	215		WITH 300 SX CMT

Well Type: OG UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/31/2016 11:00 AM  
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: 1) CIBP @ 3650' W/ 10' CEMENT ON TOP 2) CUT OFF 5 1/2" CASING @ 3500' AND PULL OUT OF HOLE 3) PERFORATE 7" CASING @ 1540', SQZ. W/ 75 SACKS CEMENT 4) PERFORATE 7" CASING @ 600', SQZ W/ 75 SACKS TO SURFACES 5) FILL 7" CASING FROM 600' TO 30' FROM SURFACE 6) CUT OFF 7" CASING AND WELD ON I.D. PLATE

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 10/31/2016 5:00 PM KCC Agent: KEN SCOFIELD

Actual Plugging Report:

SET CIBP @ 3650' WITH 5 SX CMT ON TOP. PERFORATE 7" CASING AT 1540' & TRY TO CIRCULATE WITH FRESH WATER. PUMP 2.5 BBL THEN PRESSURED UP TO 1800 PSI. PERFORATE AT 1450' & TRY TO CIRCULATE AGAIN WITHOUT SUCCESS. SPOT 35 SX CMT AT 1540'. PERFORATE 7" CASING AT 600' & ESTABLISH CIRCULATION WITH FRESH WATER. PUMP 200 SX CMT TO FILL ANNULUS & 7" CASING. HOLE & ANNULUS STANDING FULL OF CMT.

Perfs:

Top	Bot	Thru	Comments
4330	8229		

Remarks: USED COMMON CEMENT BY ORR ENTERPRISES. TMD= 8320'.

Plugged through: TBC

District: 01

RECEIVED  
NOV - 8 2016  
KCC DODGE CITY

Signed

*Ken Scofield*  
5A

(TECHNICIAN)

NOV 21 2016  
*no*