

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-193-20973-00-00
Spot: NESWSEW Sec/Twnshp/Rge: 16-9S-35W
2131 feet from N Section Line, 1900 feet from W Section Line
Lease Name: WIELAND TRUST Well #: 1-16
County: THOMAS Total Vertical Depth: 4909 feet

Operator License No.: 33768

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	303		235 sx

Op Name: FUNK PETROLEUM, LLC

Address: 2110 N. 1184TH ST
EUDORA, KS 66025

Well Type: DH

UIC Docket No:

Date/Time to Plug: 10/07/2016 12:00 PM

Plug Co. License No.: 30606

Plug Co. Name: MURFIN DRILLING CO., INC.

Proposal Revd. from: KELLY

Company: MURFIN DRILLING CO., INC.

Phone: (785) 769-6103

Proposed Plugging Method: Ordered 255 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: MARVIN MILLS

Witness Type: NONE

Date/Time Plugging Completed: 10/07/2016 5:30 PM

KCC Agent: MARVIN MILLS

Actual Plugging Report:

Perfs:

1st plug @2850 w/50 sx
2nd plug @1560 w/100 sx
3rd plug @355 w/50 sx
4th plug @40 w/10 sx

Rathole 30 sx Mousehole 15 sx

Remarks: ALLIED

Plugged through: DP

District: 04

Signed



(TECHNICIAN)

KCC WICHITA

OCT 31 2016

RECEIVED

NOV 21 2016

NO

CM

Form CP-2/3