

10-27

RECEIVED
KANSAS CORPORATION COMMISSION

2-040740

66
R

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
200 Colorado Derby Building
Wichita, Kansas 67202

NOV 19 1992

CONSERVATION DIVISION
WICHITA, KS

API NUMBER: 15-095-21,667-0000
SW SW, SECTION 21 TOWNSHIP 30 RANGE 9W

OPERATOR LICENSE # 5123 802 FEET FROM S SECTION LINE
4428 FEET FROM E SECTION LINE

OPERATOR Peckrell Drilling Co., Inc
NAME & 110 N. Market, #205
ADDRESS Wichita, KS 67202

LEASE NAME: Lauterback #B-1
COUNTY: Kingman
WELL TOTAL DEPTH: 4400' 143.00

CONDUCTOR PIPE: _____

SURFACE CASING: 8-5/8" @ 214'

ABANDONED OIL WELL _____ GAS WELL _____ INPUT WELL _____ SMD _____ D&A X

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: Clarke Corporation
ADDRESS: Medicine Lodge LICENSE: 5105

COMPANY TO PLUG AT: HOUR: _____ DAY: _____ MONTH: _____ YR: 1992

PLUGGING PROPOSAL RECEIVED FROM: Elmo Morganstien
COMPANY NAME: Clark Corp PHONE: _____

WERE: PBTD 4353' - 4-1/2" 4399' - perms 4306'-4308'

PLUGGING PROPOSAL RECEIVED BY: Steve Van Gieson

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (_____) PART (X) NONE (_____)

COMPLETED: HOUR: 1030 DAY: 27 MONTH: 10 YEAR: 1992

ACTUAL PLUGGING REPORT:
Perfs sanded back to 4250' & capped w/5 sx cmt -
4-1/2" shot loose & recovered from 3164' - pulled from
wellbore - tub run to 1405' & 30 sx cmt spotted - tub
pulled to 1004' & 30 sx spotted - tub pulled to 270'
& circ to surface


REMARKS: Allied #3444 common

INVOICED

I DID OBSERVE THIS PLUGGING.

DATE 11-24-92

INV. NO. 36884


Steve Van Gieson (AGENT)