

7-15-87

To: 6 061283
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-009-23534-0000

SE, SEC. 26, T 16 S, R 11 (W)

1980 feet from S section line

910 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 9482

Lease Name Homlka Well # 1

Operator: National Petroleum Reserves Inc.
Name & Address: 260 N. Rock Rd.
Wichita, Ks. 67206

County Barton 110.92

Well Total Depth 3413 feet

Conductor Pipe: Size 8" feet

Surface Casing: Size 8 5/8 feet 396'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address Box 347, Chase, Ks. 67524

Company to plug at: Hour: 9:00 AM Day: 15 Month: July Year: 19 87

Plugging proposal received from Mike Kelso

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2457

were: Order 100 sk 65/35 pozmix - 10% gel - 2% Econolite, 5 sk hulls.

Plugging Proposal Received by Gilbert S. Scheck (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 10:15 AM Day: 15 Month: July Year: 19 87

ACTUAL PLUGGING REPORT 8 5/8" set at 396' with 150 sks. 5 1/2" set at 3412' with 150 sks.

Top perf. at 3375' sand and 5 sks. cement

to 3325' Shot pipe 1 time and recovered 2396'. Pumped in 8 5/8", 5 sk hulls.

100 sk cement w/ 700 p.s.i.

08-07-87 AUG - 1987
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas

Remarks: By: B.J. Titen
(If additional description is necessary, use BACK of this form.)

Did you observe this plugging.

Signed Gilbert G. Scheck (TECHNICIAN)

INVOICED

DATE: 8-10-87

INV. NO. 17780