

1050179

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 055-20,003 - 0000

SW _____, SEC. 21, T 22 S, R 33 W/X
1820 feet from N/S section line
1330 feet from W/X section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5565

Lease Name Damme Well # #2 SWD

Operator: National Cooperative Refinery Assn. County Finney

Name & Address Box 6

Well Total Depth 1700 55.25 feet

Great Bend, KS 67530

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 325

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well X D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sun Oil Well Cementing License Number _____

Address Box 169, Great Bend, KS 67530

Company to plug at: Hour: 9:00 am Day: 22 Month: March Year: 19 84

Plugging proposal received from Earl Baker

(company name) NCRA (phone) 316-793-7824

were: 4 1/2 set at 1670 Baker A-1 packer stuck in hole at 1356'

Plug with 1 sack hulls and 125 sx cement down 4 1/2" production pipe

Maximum pressure 500# and shut-in pressure 100#

4 1/2" production pipe fully cemented in to surface

Plugging Proposal Received by Richard W. Lacy
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 10:20 am Day: 22 Month: March Year: 19 84

ACTUAL PLUGGING REPORT 4 1/2 set at 1670' Baker A-1 packer stuck in hole at 1356'

Plug with 1 sack hulls and 125 sx cement down 4 1/2" production pipe

Maximum pressure 500# and shut-in pressure 100#

4 1/2" production pipe fully cemented in to surface

RECEIVED
STATE CORPORATION COMMISSION
MAR 29 1984
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Use 60/40 Pozmix 2% gel 3% cc by Sun
(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

Signed Richard W. Lacy
(TECHNICIAN)

DATE 4-4-84

INV. NO. 1054 3-22