

1030189

R

To:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Not Available

SE NE SE, SEC. 28, T 22 S, R 33 (W)

1650 feet from N/S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5693

Lease Name Damme SWDW Well # 15

Operator: W. L. Hartman Estate

County Finney

Name &

Address P. O. Box 54.

Well Total Depth 5100 165.75 feet

Wichita, KS 67201

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 360

Abandoned Oil Well Gas Well Input Well SWD Well X D&A

Other well as hereinafter indicated

Plugging Contractor Allied Cement

License Number

Address Box 31, 322 West Wichita, Russell, KS 67665

Company to plug at: Hour: 12:00 pm Day: 18 Month: May Year: 19 84

Plugging proposal received from Mr. Rowley

(company name) W. L. Hartman - Garden City (phone) 316-277-2511

were: 4 1/2 set at 5100'

pump 4 1/2' and annulus at the same time with 500 sx cement and shut in

Plugging Proposal Received by Steve Hrusina
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 2:00 pm Day: 18 Month: May Year: 19 84

ACTUAL PLUGGING REPORT 4 1/2" casing collapsed at 1638'

pumped 250 sx cement through 4 1/2" and annulus at the same time. Redi-mix at 210' to top

Maximum pressure 300# and shut in pressure 0

Leon Ditus observed the plugging

RECEIVED
STATE CORPORATION COMMISSION

JUN 01 1984

Remarks: No pipe recovery. Used 60/40 Pozmix 2% gel 3% cc by Allied.
(If additional description is necessary, use BACK of this form.)CONSERVATION DIVISION
Wichita, Kansas

INVOICED

(If additional description is necessary, use BACK of this form.)

Signed Steve Hrusina
(TECHNICIAN)

DATE

INV. NO.

JUN 08 1984

JUL 17 1984