

\*\*\*REPLUG\*\*\*

1090196

\*\*\*REPLUG\*\*\*

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-083-21089 A

NW-SE-NE 1/4, SEC. 18, T 22 S, R 21 WXX

1650 feet from ~~N~~ section line

990 feet from ~~SE~~/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5004

Lease Name KORF Well # 1

Operator: Vincent Oil Corporation

County Hodgeman

Name & Address 125 N. Market #1110

Well Total Depth 4574 feet

Wichita, KS 67202

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 290

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated Replug of OWWO

Plugging Contractor Hembree Well Service License Number 6907

Address 302 E. Sycamore, P.O. Box 458, Ness City, KS 67560

Company to plug at: Hour: 8 am Day: 26 Month: June Year: 19 84

Plugging proposal received from Chuck Schmidt

(company name) Vincent Oil Corporation (phone) 316-262-3573

were: To run tubing into hole to a depth of 552', load the hole with mud and spot plugs at 552 feet with 75 sacks cement, pull up to 40 feet and build a solid bridge with hulls, push down a wood and rubber plug and spot 15 sacks of cement from 40 feet to the surface.

Plugging Proposal Received by R Barburton  
(TECHNICIAN)

Plugging Operations attended by Agent?: All XX Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 3:20 p.m. Day: 26 Month: June Year: 19 84

ACTUAL PLUGGING REPORT Ran tubing to 552 feet, mixed and pumped 1/2 sack hulls and then loaded the hole with gel. Mixed and spotted 75 sacks cement, pulled out of hole and waited on cement. After 1 1/2 hours, ran in hole and tagged cement at 412 feet. Spotted 18 sacks at 412 feet and pulled out of hole. Brought mud up to 30 feet, put in 1/2 sack hulls, pushed down a wood and rubber plug to 30 feet and filled hole to surface with 12 sacks cement. Cemented with Class A using 3% CaCl.

Remarks: Cementing by Halliburton-Ticket # 824603

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE No charge

INV. NO. 6-26

RECEIVED  
STATE CORPORATION COMMISSION

JUL 11 1984

CONSERVATION DIVISION  
Wichita, Kansas

Signed R Barburton  
(TECHNICIAN)