

To: 1 030543
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 083-21,216-0000
C NW SW, SEC. 20, T. 22 S, R. 21 W EX

TECHNICIAN'S PLUGGING REPORT

Operator License # 5430

Operator: Energy Three, Inc.
Name & Address: P. O. Box 1505
Great Bend, KS 67530

1980 feet from S section line
4620 feet from E section line

Lease Name Salmans Well # 1
County Hodgeman 147.06
Well Total Depth 4525 Mississippi feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1090

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Big Three Drilling, Inc. License Number 5836
Address P. O. Box 52, Gorham, KS 67640

Company to plug at: Hour: 1:00 am Day: 4 Month: October Year: 19 85

Plugging proposal received from Stan Lovelady
(company name) Big Three (phone) 316-792-5968

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1347'
Elevation 2202'

- 1st plug at the base of the Anhydrite with 50 sx cement
- 2nd plug 30' below the base of the surface pipe with 40 sx cement
- 3rd plug at 510' with 25 sx cement
solid bridge
- 4th plug hulls - plug at 40' -- cement to surface with 10 sx cement
- 6th plug to circulate rat hole with 10 sx cement, 7th plug to circulate mouse hole with 10 sx cement

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 2:30 am Day: 4 Month: October Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 1356' with 50 sx cement, 2nd plug at 1110' with 40 sx cement, 3rd plug at 510' with 25 sx cement, 4th & 5th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement. 6th plug to circulate rat hole with 10 sx cement, 7th plug to circulate mouse hole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED
DATE 10-15-85
INV. NO. 10567
10-4

RECEIVED
OCT 10 1985
Signed Steve Durrant
(TECHNICIAN)

CONSERVATION DIVISION
Wichita, Kansas 10-10-85