

6060128

15-009-20899-0000

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15

NE, Sec. 26, T 16 S, R 11 W1/4

2310 feet from N1/4 section line

380 feet from NE section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5886

Lease Name Kuier Well # 2

Operator: Chief Drilling Co. Inc.  
Name &  
Address Century Plaza, Wichita, Ks  
67202

County Barton

Well Total Depth 3376 feet 109.72

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8" feet 353

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 176, Chase, Ks 67524

Company to plug at: Hour: 10:00 AM Day: 17 Month: Jan Year: 1984

VERBAL PLUGGING ORDERS GIVEN TO Neal Peddicord

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: Order 165 sh. 5/8" p.c., 4" gel. - 3% gel. d., 15 sh. gel., 5 sh. bulls  
& 8 5/8" plug.

Signed Paul G. Kubi  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 2:30 PM Day: 17 Month: Jan Year: 1984

ACTUAL PLUGGING REPORT 8 5/8" - 353' w/ 250 sh., 4 1/2" set at 3371' w/ 125 sh.,  
P.B. to 3368'. Top perf. at 3352'. Plugged bottom w/ 4 sh.  
cement, sand & 4 sh. cement to 3300'. Shot pipe 2 times & recovered  
2393'. Pumped in 8 5/8" - 4 sh. bulls, 25 sh. cement, 12 sh. gel., 40 sh.  
cement, 3 sh. gel., 1 sh. bulls, released plug & followed w/ 100 sh. cement w/  
800 pounds pressure.

Remarks: By Allied cementing

I hereby certify that the above plugging instructions were given as herein stated and that I (did / ~~did not~~) observe this plugging.

RECEIVED  
STATE CORPORATION COMMISSION  
INVOICED  
DATE 1-25-84 JAN 23 1984 01-23-84  
CONSERVATION DIVISION  
Wichita, Kansas  
INV. NO. 9248-10

Signed Paul G. Kubi  
(TECHNICIAN)