

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
July 2014  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

OPERATOR: License #: 34798  
Name: Viking Production, LLC  
Address 1: 1432 Nighthawk Rd  
Address 2: \_\_\_\_\_  
City: Yates Center State: KS Zip: 66783 + \_\_\_\_\_  
Contact Person: Bert Carlson  
Phone: ( 620 ) 485-6064  
Type of Well: (Check one)  Oil Well  Gas Well  OG  D&A  Cathodic  
 Water Supply Well  Other: \_\_\_\_\_  SWD Permit #: \_\_\_\_\_  
 ENHR Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
LAYTON Depth to Top: 1867 Bottom: 1871 T.D. 1943  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API No. 15 - 035-24369-00-00  
Spot Description: SE SW NW NW  
\_\_\_\_\_ Sec. 17 Twp. 32 S. R. 8  East  West  
4,241 Feet from  North /  South Line of Section  
4,945 Feet from  East /  West Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
County: COWLEY  
Lease Name: BUTTS Well #: 17-2  
Date Well Completed: \_\_\_\_\_  
The plugging proposal was approved on: \_\_\_\_\_ (Date)  
by: DUANE KRUEGER (KCC District Agent's Name)  
Plugging Commenced: 07-18-2016  
Plugging Completed: 08-04-2016

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
LAYTON	OIL/GAS	PROD	4.5	1943	694

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

RIH w/TBG @1800', Snyder cementing mixed and pumped 20 SxS class A common and displaced in casing, tagged cement plug @ 1682'. RIH on wireline cut casing @ 913', 821', and 694', layed down 23 joints 4-1/2' casing (694'), RIH w/TBG @515', Snyder cementing mixed and pumped 120 SxS class A common, cement did not circulate. 08-04-2016, tagged cement plug@110' RIH w/TBG @ 95', Snyder cementing established circulation, mixed and pump 40 SxS class A common to surface, cement circulated.

Received  
KANSAS CORPORATION COMMISSION  
Plugging Contractor License #: 35164 Name: Jim Synder, Inc.  
Address 1: PO Box 109 Address 2: \_\_\_\_\_  
City: Hamilton CONSERVATION DIVISION WICHITA, KS State: Kansas Zip: 66853 + 0109  
Phone: ( 620 ) 344-6283  
Name of Party Responsible for Plugging Fees: Viking Production, LLC  
State of Kansas County, Woodson, ss.  
Bert Carlson  Employee of Operator or  Operator on above-described well,  
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God

Signature: Bert Carlson