

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
July 2014
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 34798
Name: Viking Production, LLC
Address 1: 1432 Nighthawk Rd
Address 2: _____
City: Yates Center State: KS Zip: 66783 + _____
Contact Person: Bert Carlson
Phone: (620) 485-6064
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
LAYTON Depth to Top: 1926 Bottom: 1930 T.D. 1940
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 035-24368-00-00
Spot Description: SW SE SW SW
_____ Sec. 8 Twp. 32 S. R. 8 East West
283 Feet from North / South Line of Section
4,615 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: COWLEY
Lease Name: BUTTS Well #: 1-AUG
Date Well Completed: 07-05-2016
The plugging proposal was approved on: _____ (Date)
by: DUANE KRUEGER (KCC District Agent's Name)
Plugging Commenced: _____
Plugging Completed: 07-05-2016

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
LAYTON	O/G	PROD	4.5	1940	525

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

RIH w/TBG @1910', Snyder Cementing Mixed and pumped 20 SxS class A common and displaced in casing, tagged cement plug @ 1835'. RIH on wireline cut casing @550', layed down 11 joints 4-1/2" casing. 07-01-2016, RIH w/TBG @525', Snyder Cementing mixed and pumped 100 SxS class A common, cement did not circulate, 07-05-2016 tagged cement plug @100', RIH w/TBG @ 95', Snyder mixed and pumped 40 SxS class A common to surface tagged cement plug #31', Snyder topped well back to surface w/10 SxS.

Plugging Contractor License #: 35164 Name: Jim Synder, Inc.
Address 1: PO Box 109 Address 2: _____
City: Hamilton State: Kansas Zip: 66853 + 0109
Phone: (620) 344-6283
Name of Party Responsible for Plugging Fees: Viking Production, LLC
State of Kansas County, Woodson, ss.
Bert Carlson Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.
Signature: Bert Carlson