

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Kingman SEC. 21 TWP. 30 RGE. 9w E/W
Location as in quarters or footage from lines:
NE NE NW

	o		

Lease Owner E H Wood Jr.
Lease Name Hawley Well No. 1
Office Address 301 Farmers & Bankers Bldg. Wichita Ks.
Character of Well (Completed as Oil, Gas or Dry Hole): Oil/WO
Date Well Completed _____
Application for plugging filed 8-17-82
Plugging commenced _____
Plugging completed 9-8-82
Reason for abandonment of well or producing formation _____

Locate Well
correctly on above
Section Platt.

Depleted
Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Maurice Leslie
Producing formation _____ Depth to top _____ bottom T.D. 4393
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8	308	none
				4 1/2	4383	2896

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Sanded Hole to 4360 Set Four sks. cement with bailer
Recovered 2896' of 4 1/2" casing
Pumped 25 sks. Gel 6 sks. Hulls 150 sks. cement

RECEIVED
STATE CORPORATION COMMISSION

OCT 26 1982

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Voth Casing Pulling

STATE OF Kansas COUNTY OF Cowley, ss.

(employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) Walter Voth
715 South A Arkansas City Ks.
(Address)

SUBSCRIBED AND SWORN TO before me this 21 day of Oct, 19 82



Milton Harris
Notary Public.

My Commission expires: _____

Sunray Mid-Continent Oil Company
Tulsa, Oklahoma

Tulsa, Oklahoma
March 3, 1958

CONTRACTOR: Stickle Drilling Company
Drilling Commenced: February 11, 1958
Drilling Completed: February 28, 1958

Hawley #1 NW/4 Section
21-30S-9W, Kingman
County, Kansas.

DRILLERS LOG

Depth Figures indicate base of formation:

Surface	0
Clay & Sand	40
Sand	110
Shale & Shells	960
Shale & Anhydrite Streak	1210
Shale & Shells	1400
Lime & Shale	2290
Shale & Lime	2715
Lime	2735
Shale & Lime	2835
Lime & Shale	3010
Shale & Lime	3090
Lime & Shale	3360
Lime	3400
Lime & Shale	3550
Shale & Lime	3635
Lime & Shale	3715
Lime	4155
Lime & Shale	4290
Lime & Shale With Chert	4320
Mississippi Chert	4339
Chat	4392
Lime	4400 TD

I, Frank E. Stickle, hereby certify the above to be a true and complete Drillers Log of Sunray Mid-Continent Oil Company's P. Hawley #1 NW/4 Section 21-30S-9W, Kingman County, Kansas.

Frank E. Stickle
Frank E. Stickle

Lillian T. Bonham
Notary Public

February 13, 1960
My Commission Expires

PLUGGING
SEC 21T. 30S. 9W
PAGE 86 LINE 9D

STICKLE
WICKS