


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas



Locate well correctly on above
Section Plat

Kingman County, Sec 21 Twp 30 Rge 9 (E) W (W)
Location as "NE/CNW/SW" or footage from line N/2 NE SE
Lease Owner Pickrell Drilling Co.
Lease Name Swingle "J" Well No. 1
Office Address 705 Fourth Natl Bank Bldg. Wichita, Ks. 67202
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed March 22, 1967
Application for plugging filed Feb. 28, 1969
Application for plugging approved Mar. 3, 1969
Plugging commenced Mar. 10, 1969
Plugging completed Mar. 13, 1969
Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production October, 1968
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ralph Warren
Producing formation Mississippian Depth to top _____ Bottom _____ Total Depth of Well 4400 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	203'	None
				5 1/2	4399'	3444'
RECEIVED STATE CORPORATION COMMISSION APR 3 1969 CONSERVATION DIVISION Wichita, Kansas						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged Back with sand from 4366' to 4280'. Mixed and dumped 5 sx. of cement from 4280' to 4240'. Pulled casing. Mudded hole to 200'. Set 10' rock bridge from 200' to 190'. Mixed and dumped 25 sx. of cement from 190' to 115'. Mudded hole from 115' to 40'. Set 10' rock bridge from 40' to 30'. Mixed and dumped 10 sx. of cement from 30' to base of the cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Russ Casing Pulling Inc.
Address Box 1082 Great Bend Ks.

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
C. W. Sebits ~~employer of above~~ (owner or operator) of the above-described


well, being first ~~sworn~~ sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well and that the same are true and correct. So help me God.

(Signature) [Signature]
C. W. Sebits, Partner & Attorney-in-Fact
705 4th Nat'l Bank Bldg, Wichita, Ks. 67202
(Address)

Subscribed and sworn to before me this 2nd day of April, 19 69

My commission expires May 10, 1970

[Signature]
L. M. WHITING
Notary Public.



ROTARY DRILLING LOG

COMPANY: Pickrell Drilling Company Rotary Drilling Commenced 1/28/67
 705 Fourth National Bank Bldg.
 Wichita, Kansas Rotary Drilling Completed 2/8/67

LOCATION: C N/2 NE SE Section 21-30S-9W } Swingle "I" No. 1
 Kingman County, Kansas }

CONTRACTOR: **PICKRELL DRILLING COMPANY**
 Wichita, Kansas

CASING RECORD: (9 Jts.) 8 5/8" surface casing set @ 203' and cemented with 165 sacks
 cement. Circulated. (144 Jts.) 5 1/2" casing set @ 4399' and cemented
 125 sacks cement. Complete @ 4:45 PM, February 8, 1967.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

RECEIVED
 STATE CORPORATION COMMISSION
 APR 3 1969
 CONSERVATION DIVISION
 Wichita, Kansas

C. F. S.

70	Sand	4302
100	Red Rock	4318
204	Red Rock	4338
610	Shale	4353
1515	Shale, Shells & Lime	
3380	Lime & Shale	
3515	Shale, Lime & Sand	
3665	Lime & Shale	
3790	Lime	
3829	Lime & Shale	
3890	Lime	
3988	Lime & Shale	
4050	Lime	
4318	Lime & Shale	
4400	Mississippian, RTD	

Slope Tests

2500
3000
3500
4000

S. L. M.
3829

The undersigned, C. W. SEBITS, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY
 By [Signature]
 C. W. SEBITS, Attorney-in-Fact

STATE OF KANSAS }
 COUNTY OF SEDGWICK } ss.:

On this 17th day of February, 1967, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. SEBITS, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.
 My commission expires: May 10, 1970

[Signature]
 L. M. Whiting
 Notary Public