


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

15-009-15029-0000
WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Barton County, Sec. 26 Twp. 26 Rge. 11 (W)
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines ~~SW NE SW~~ SW $\frac{1}{4}$ SW ANE 100
Lease Owner The El Dorado Refining Company
Lease Name Kraft Well No. 2
Office Address Box 209 Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed September 30 19 51
Application for plugging filed June 11 19 56
Application for plugging approved June 12 19 56
Plugging commenced June 28 19 56
Plugging completed July 2 19 56
Reason for abandonment of well or producing formation Insufficient Production

If a producing well is abandoned, date of last production June 26 19 56
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. R. M. Brundage Box 283 Hoisington, Kansas
Producing formation Arbuckle Lime Depth to top 3361 Bottom 3366 Total Depth of Well 3379 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	310'	none
				5 1/2"	3382	2921, 50'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with sand to 3350'
Run 5 sacks of cement at 3350'
Mudded to 300'
Set rock bridge to 285'
Run 20 sacks of cement at 285'
Mudded to 35' Set rock bridge to 30'
Run 10 sacks of cement to cap.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor G. E. Shull Casing Pulling Company
Address Box 558 Great Bend, Kansas

STATE OF KANSAS, COUNTY OF RUSSELL, SS.
LEVI B. SHERMAN (employee of owner) or (owner/operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Levi B. Sherman
Box 209 Russell, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 6th day of July, 19 56

My commission expires 5 - 9 - 59

Carol J. Miller
Notary Public

23-8390-s 6-51-20M

PLUGGING
FILE SEC. 26 T. 16 R. 11W
BOOK PAGE 70 LINE 33

07-09-56

STERLING DRILLING CO.

Sterling, Kansas

WELL LOG-----KRAFT #2

Location - SW/4 NW/4 SW/4 of Section 26-16s-11w, Barton County, Kansas

OWNER - The El Dorado Refining Company
 ROTARY DRILLING CONTRACTOR - Sterling Drilling Company
 CABLE TOOL CONTRACTOR -

Commenced - 9-19-51
 Completed - 9-30-51 (w/r)
 (w/c.t.)

Total Depth - 3366' (w/r) 3364 D. F.
 3379 (w/c.t.) D. F.

LOG

0 - 745	Shale and Shells
745 - 775	Anhydrite
775 - 1100	Shale and Shells
1100 - 1750	Lime and Shale
1750 - 2010	Lime
2010 - 2690	Shale and Lime
2690 - 2990	Lime
2990 - 3069	Lime and Shale
3069 - 3361	Lime
3361 - 3366	Arbuckle Lime

D. P. & C. 01 to 3364 RTD. 100' OIH o'nite.
 D.D. 3376; 2000' OIH/15 hrs. 5 BOPH/3 hrs.
 D.D. 3379 T. D. no increase; F. U. 1750' OIH/13 hrs.

No perforations.

CASING RECORD

310' of 8 5/8" surface pipe, cemented with 175 sacks cement.

3382' of 5 1/2" O. D. Casing cemented at 3363' with 70 sacks cement.

PRODUCTION: 173 BOPD

ELEVATION: 1925'

FORMATION TOPS: D.F.

Heebner	2964
Toronto	2984
Brown Lime	3066
Lansing	3080
No Congl.	
Arbuckle	3359

COPY

PLUGGING
 FILE SEC. 26 16 R 11W
 BOOK PAGE 10 LINE 33