

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

Barton

County, Sec. 26 Twp. 16 Rge. (E) 11 (W)

Location as "NE/CNW/SW" or footage from lines NE/4 SW/4 SE/4

Lease Owner The Derby Oil Company

Lease Name Homolka Well No. 2

Office Address Box 1030, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed September 24, 19 54

Application for plugging filed September 25, 19 54

Application for plugging approved September 25, 19 54


Plugging commenced September 25, 19 54

Plugging completed September 25, 19 54

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Warren H. Horner

Producing formation Depth to top Bottom Total Depth of Well 3397 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	311	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mud to 3001'  
Plug @ 3001' w/20 sacks cement  
Mud to 45'  
Plug @ 45' w/14 sacks cement

Rup  
10-16-54

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Badger Drillers, Inc.

Address 1435 Wilson, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Bill K. Henrichs (employee of owner) or (owner/representative) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bill K. Henrichs

Box 1030, Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 14th day of October, 19 54

Notary Public

My commission expires August 24, 1957

PLUGGING  
BOOK PAGE 166 LINE 3  
SEC 26 T 16 R 11W


# THE DERBY OIL COMPANY

## WELL RECORD

PRODUCTION DEPARTMENT

640 Acres

N



LEASE Homolka WELL NO. 2

RECORD COMPILED October 1, 1954 BY Bill K. Henrichs

LOCATION NE SW SE ACRES 160

1650 FT. FROM East LINE 990 FT. FROM South LINE OF

SEC. 26 TWP. 16 RGE. 11 COUNTY Barton STATE Kan.

STAKED BY Don Bowman DATE September 13, 1954

ELEVATION: GND. 1914 D.F. 1916 K.B. 1918

ALL MEASUREMENTS ARE FROM Kelly Bushing WHICH IS

         FT. ABOVE BRADEN HEAD.

POOL: Kraft-Prusa

TOOLS	STARTED	COMPLETED	FROM	TO	CONTRACTOR
ROTARY	9/16/54	9/25/54	0	3397	Badger Drlg. Co.
CABLE					

### PRODUCTION DATA

DATE	OIL	WATER	TYPE OF TEST	REMARKS

### CASING AND TUBING RECORD

SIZE HOLE DRILLED	DEPTH	CASING SIZE	WT.	THDS.	MAKE, TYPE, GRADE, NEW, USED	CASING POINT	CEMENT			REMARKS
							SACKS	TYPE	ESTIMATED TOP	
12 $\frac{1}{4}$ IN.	311	8 5/8	24#	8 rd	New, J-55, ss	311	200	Portland	Surface	300# C.C., Globe

#### SCRATCHERS

#### CENTRALIZERS

#### FLOAT EQUIPMENT

FROM	TO	NO.	DEPTH	NO.

**PLUGGING**  
 FROM SEC 26 T 16 R 11  
 FROM FACE 160 LINE 3

STARTED  
 0  
 CONCRETE  
 100# C.C., Globe



# WELL RECORD-(CONTINUED)

WELL NO. 2

LEASE Homolka

## DRILL STEM TESTS

FORMATION TESTED	FROM	TO	TIME OPEN	RESULTS (Blow, Recovery, BHP, FP)
Lansing	3148	3160	45"	Good blow 45", rec. 60' OCM plus 60' O&WCM, BHP 555#.

## SURVEYS (LOGS)

TYPE	COMPANY	DATE

## COMPLETION RECORD

Dry and Abandoned

# WELL RECORD - (CONTINUED)

## ACIDIZING RECORD

DATE					
QUANTITY (GALS.)					
MAX. TUB. PR.					
MAX. CAS'G PR.					
BLANKET					
HOURS					
METHOD					
OIL BEFORE					
OIL AFTER					
WATER BEFORE					
WATER AFTER					
DONE BY					

### DEFLECTION

### PLUGGING RECORD

DEPTH	ANGLE	V. CORR.	
			START <u>September 25,</u> 19 <u>54</u> FINISH <u>September 25,</u> 19 <u>54</u> GIVE RECORD OF PLUGS DRIVEN, CEMENT, ROCK, ETC., MUD AND HOW PLACED, AND ALL PIPE LEFT IN HOLE.
500'	1/2°		
1000'	1/4°		Mud to 3001'
1500'	0°		'Plug @ 3001' w/20 sax cement
2000'	1/4°		Mud to 45'
2500'	0°		Plug @ 45' w/14 sacks cement
3000'	1°		
			311' - 8 5/8" surface casing left in hole

### ADDITIONAL INFORMATION & RECOMMENDATIONS