

STATE OF KANSAS
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

15-009-21114-0000

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Barton County, Sec. 26 Twp. 16 Rge. 11 E/W
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines
NE NESE

Lease Owner Chief Drilling Company
Lease Name Homolka #1 Well No. _____
Office Address Wichita, Kansas 67202
Character of Well (Completed as Oil, Gas or Dry Hole) _____



Locate well correctly on above
Section Plot

Date Well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 11/8/77 _____ 19____
Plugging completed 11/17/77 _____ 19____
Reason for abandonment of well or producing formation
depleted.

If a producing well is abandoned, date of last production
_____ 19____

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes _____

Name of Conservation Agent who supervised plugging of this well Rankin
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3383
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	347	none
				4 1/2"	3381	2610

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from _____ feet to
_____ feet for each plug set.

Sanded to 3350' and ran 4 sacks cement. Cut poorboy head off and loaded hole.
Shot pipe at 2603', pulled 81 joints. Pumped 25 sacks gel, 4 sacks hulls, 100
sacks cement, 5% gel.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION

NOV 22 1977 11-22-77

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KELSO CASING PULLING
CHASE, KANSAS
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS COUNTY OF RICE, ss.
R. DARRELL KELSO (employee of owner) or (owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
CHASE, KANSAS

(Address)

SUBSCRIBED AND SWORN TO before me this 18th day of November, 1977

My commission expires



Margaret Melcher
Notary Public.

March 7, 1977

DRILLERS LOG

#1 Homolka
NE NE SE
Sec. 26-16S-11W
Barton County, Kansas

OPERATOR: Chief Drilling Co., Inc.
CONTRACTOR: B & B Drilling, Inc.
COMMENCED: February 25, 1977
COMPLETED: March 3, 1977

8 5/8" @ 347' w/175 sx

0	354	Shale, Shells & Sand
354	706	Shale & Sand
706	725	Anhydrite
725	801	Shale & Sand
801	2545	Shale
2545	2992	Shale & Lime
2992	3383	Lime
3383		RTD

RECEIVED
STATE CORPORATION COMMISSION

NOV 09 1977

CONSERVATION DIVISION
Wichita, Kansas

4 1/2" @ 3381' w/150 sx

We certify that the above and foregoing is a true and correct copy of the log on the #1 Homolka located in Barton County, Kansas.

B. & B DRILLING, INC.

Bill Lahar

Bill Lahar

Subscribed and sworn to before me this 7th day of March, 1977.

Betty M. Abbott
Betty M. Abbott Notary Public

My Commission Expires:

January 22, 1979

