

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER None
LEASE NAME Damme
WELL NUMBER 2
SPOT LOCATION Approx C SW/4
SEC. 21 TWP. 22 RGE. 33 (E) (W)
COUNTY Finney
Date Well Completed 10-15-67
Plugging Commenced 3-22-84
Plugging Completed 3-30-84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR NCRA
ADDRESS Box 6, Great Bend, Ks. 67530

PHONE # (316) 793-7824 OPERATORS LICENSE NO. 5565

Character of Well SWD
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City, Ks.-State Rep. Mr. Richard Lacey

Is ACO-1 filed? No If not, is well log attached? Yes

Producing formation _____ Depth to top _____ bottom _____ T.O. 1660' PBTD
1700' RTD

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	325	-0-
				4 1/2	1670	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Sun Oilwell Cementing Co. cemented w/2 sx. hulls and 125 sxs 60/40 Poz. w/2% gel and 3% CaCl. Max. press 500# - finished @ 100#. On slight vac. in 1 min (10:30 a.m.). Shut in 4 hrs. Run wireline. FI. @ 45' and top of cement @ 319'. Wait 1 week. Dump 1 1/2 yard Redi-Mix down 4 1/2" csg. Hole stayed full of cement. Complete 9:30 a.m. 3-30-84.

(If additional description is necessary, use BACK of this form.)


Name of Plugging Contractor None License No. _____
Address _____

Rec'd 4-6-84

STATE OF KANSAS COUNTY OF BARTON, ss.

I. J. Gotsche (employee of operator) or
(~~operator~~) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]
I. J. Gotsche
(Address) Box 6, Great Bend, Ks.



SUBSCRIBED AND SWORN TO before me this 5th day of April, 1984

Patricia Schultz
Notary Public
Patricia Schultz

My Commission expires: January 29, 1985

RECEIVED
STATE CORPORATION COMMISSION

APR 06 1984

CONSERVATION DIVISION
Wichita, Kansas

15

12

12

DRILLER'S LOG

COMPANY: National Cooperative Refinery Association
 CONTRACTOR: LEBEN DRILLING, INC.
 FARM: DAME #2 SWDW
 LOCATION: SW 1/4 SECTION 21-22S-33W
 FINNEY COUNTY, KANSAS
 COMMENCED: 10-3-67
 COMPLETED: 10-5-67

0	135	Surface Soil
135	170	Sand
170	1370	Shale
1370	1521	Redbed, Shale
1521	1700	Sand, Shale
	1700	RTD - Set 4 1/2" Casing


2 5/8" used surface casing set @ 325' cemented with 210 sacks of Common, 2% cc

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Dame #2 Salt Water Disposal Well, located Southwest Quarter (SW 1/4) of Section 21, Township 22 south, Range 33 West, Finney County, Kansas, as reflected by the records of Leben Drilling, Inc.

Leslie Kite
 Leslie Kite

STATE OF KANSAS)
) SS
 COUNTY OF BARTON)

Subscribed and sworn to and before me, a Notary Public, in Finney County, Kansas, this 10th day of October, 1967.



Ulanda Nichols
 Ulanda Nichols

My Commission Expires:
 April 1, 1971

RECEIVED
 STATE CORPORATION COMMISSION
 APR 06 1984
 CONSERVATION DIVISION
 Wichita, Kansas