

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-195-60010-00011

LEASE NAME Nagel

WELL NUMBER #1

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

         Ft. from S Section Line

         Ft. from E Section Line  
NE/2 NE SW

SEC. 3 TWP. 24S RGE. 15W (E) or (W)

LEASE OPERATOR Tomlinson Oil Company

ADDRESS P.O. Box 1588 Great Bend, Kansas 67530

COUNTY Stafford

PHONE# (316) 792-1588 OPERATORS LICENSE NO. 5025

Date Well Completed         

Character of Well Oil

Plugging Commenced 12-24-86

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 12-30-86

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? Dodge City, Kansas

Is ACO-1 filed?          If not, Is well log attached?         

Producing Formation          Depth to Top          Bottom          T.D. 4099'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size   | Put in | Pulled out |
|-----------|---------|------|----|--------|--------|------------|
|           |         |      |    | 8-5/8" | 243'   | none       |
|           |         |      |    | 5-1/2" | 4097'  | 2063'      |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Pumped bottom with 160 sacks common mixed with 2 sacks hulls. Shot pipe @2520', 2423', 2208', 2063' and pulled a total of 63 joints of 5-1/2" casing. Plugged surface with 3 sks. hulls, 10 sks. gel, 50 sks. cement, 10 sks. gel, 1 sk. hulls, released plug and 125 sks. cement, 60/40 pos, 6% gel. Plugging Complete.  
(if additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling, Inc. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso, President (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347 Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 23rd day of January, 1987

Jane Hoover  
Notary Public

STATE CORPORATION COMMISSION

JAN 26 1987  
CONSERVATION DIVISION  
Wichita, Kansas

My Commission Expires:



1-26-87

414 UNION CENTER

PHONE AM 7-8062

VIENNA, MISSISSIPPI

September 2, 1963

OCT 28 1963

Toulinson-Kathol, Inc.  
 414 Union Center  
 Vienna, Kansas

Re: Toulinson-Kathol, Inc.  
 C 1 Well  
 N/2 12 SW, Sec. 3-24-13W  
 Stafford County, Kansas

Dear Sirs:

The following is a sample analysis report of the above captioned well.

The well was under geological supervision from 3800 to 4099 feet, rotary total depth. Samples were examined from 3200 to 4099 feet, rotary total depth.

All tops and zones of porosity are based on Kelly bushing measurements.

All stratigraphic tops were determined from sample examination:

Elevation - 2020 feet

|                    |      |       |
|--------------------|------|-------|
| Top Washnet        | 3478 | -1458 |
| Top Brown Linn     | 3512 | -1592 |
| Top Leaning        | 3633 | -1713 |
| Top Mississippia   | 3783 | -1863 |
| Top Viola          | 4020 | -2100 |
| Top Simpson Shale  | 4001 | -2081 |
| Top Simpson Sand   | 4051 | -2031 |
| 5 1/2" Casing      | 4577 | -2557 |
| Top Artesian       | 4061 | -2061 |
| Rotary Total Depth | 4099 | -2079 |