

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 COLORADO DERRY BUILDING  
WICHITA, KANSAS 67202

WELL PLUGGING RECORD

API NUMBER 15-083-21,089-0000

LEASE NAME Korf

WELL NUMBER #1

SPOT LOCATION NW SE NE

SEC. 18 TWP. 22 RGE. 21 (X) OR (W)

COUNTY Hodgeman

DATE WELL COMPLETED 11-21-83

~~PLUGGING COMMENCED~~

PLUGGING COMPLETED 6 am. 11-21-83

TYPE OR PRINT  
PLEASE FILL OUT COMPLETELY  
AND MAKE REQUIRED AFFIDAVIT.

LEASE OPERATOR Vincent Oil Corporation

ADDRESS 125 N. Market Suite 1110  
Wichita, KS 67202

PHONE # (316) 262-3573 OPERATORS LICENSE NO. 5004

CHARACTER OF WELL  
(OIL, GAS, D&A, SWD, INPUT, WATER SUPPLY WELL)

DID YOU NOTIFY THE KCC/KDHE JOINT DISTRICT OFFICE PRIOR TO PLUGGING THIS WELL? Yes

WHICH KCC/KDHE JOINT OFFICE DID YOU NOTIFY? Dodge City, Ks

IS ACC-1 FILED? \_\_\_\_\_ IF NOT, IS WELL LOG ATTACHED? \_\_\_\_\_

PRODUCING FORMATION \_\_\_\_\_ DEPTH TO TOP \_\_\_\_\_ BOTTOM \_\_\_\_\_ T.D. 4477

SHOW DEPTH AND THICKNESS OF ALL WATER, OIL AND GAS FORMATIONS.

OIL, GAS OR WATER RECORDS | CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

DESCRIBE IN DETAIL THE MANNER IN WHICH THE WELL WAS PLUGGED, INDICATING WHERE THE MUD FLUID WAS PLACED AND THE METHOD OR METHODS USED IN INTRODUCING IT INTO THE HOLE. IF CEMENT OR OTHER PLUGS WERE USED STATE THE CHARACTER OF SAME AND DEPTH PLACED, FROM FEET TO FEET EACH SET. plugged with 160 sxs 60/40 poz, 2% gel, 3% cc as follows; 1350' - 50 sxs; 750' - 50 sxs; 390' 40 sxs; 40' - 10 sxs; rathole- 10 sxs

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

NAME OF PLUGGING CONTRACTOR Wheatstate Oilfield Services, Inc. LICENSE No. 5149-87  
ADDRESS P.O. Box 329 Pratt, KS 67124

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

RICHARD A. HIEBSCH (EMPLOYEE OF OPERATOR) OR (OPERATOR) OF ABOVE-DESCRIBED WELL, BEING FIRST DULY SWORN ON OATH, SAYS: THAT I HAVE KNOWLEDGE OF THE FACTS, STATEMENTS, AND MATTERS HEREIN CONTAINED AND THE LOG OF THE ABOVE-DESCRIBED WELL AS FILED THAT THE SAME ARE TRUE AND CORRECT, SO HELP ME GOD.

(SIGNATURE) Richard A. Hiebsch  
RICHARD A. HIEBSCH  
(ADDRESS) 125 N. Market, #1110  
Wichita, KS 67202


SUBSCRIBED AND SWORN TO BEFORE ME THIS 21st DAY OF November, 19 83

Ruth N. Benjamin  
Ruth N. Benjamin  
NOTARY PUBLIC


MY COMMISSION EXPIRES: June 17, 1985

RECEIVED  
STATE CORPORATION COMMISSION

DEC 27 1983



FORM CP-4  
REVISED 06-83



**Oilfield Services, Inc.**

15-083-21089-0000

- Rotary Drilling
- Drilling Mud and Chemicals
- Heavy Oil Field Hauling
- Roustabout and Dirt Services
- Well Completion and Servicing Units

DRILLERS' WELL LOG

KORF #1  
 NW/4 SE/4 NE/4 Sec. 18-22-21W  
 Hodgeman County, Kansas  
 Commenced : 11-10-83  
 Completed : 11-21-83  
 API# 15-083-21,089  
 Operator : Vincent Oil Corporation

Depth		Formation	Remarks
From	To		
-0-	406	Sand, Clay	Set 8 5/8", new 24# surface casing.
406	1245	Sand, Clay	Cement by Buie with 225 sxs Class H cement
1245	1315	Shale, Sand, Clay	3% cc. Cement did circulate. Plug down at 12:45 a.m. on November 11, 1983.
1315	1360	Anhydrite	Surface set at 399'.
1360	1460	Shale	RTD 4477'
1460	2320	Shale, Sand	Plugged with 160 sxs 60/40 poz, 2% gel, 3% cc as follows: 1350' - 50 sxs; 750' - 50 sxs; 390' - 40 sxs; 40' - 10 sxs; rat hole - 10 sxs. Cement by Buie Company Plug down at 6:00 a.m. on November 21, 1983. State Plugging Office contacted was Dodge City, Kansas.
2320	4477	Shale, Lime, T.D.	

STATE OF KANSAS )  
 ) ss  
 COUNTY OF PRATT )

I, the undersigned, being duly sworn on oath, state that the above Drillers' Log is true and correct to the best of my knowledge and belief and according to the records of this office.

WHEATSTATE OILFIELD SERVICES, INC.

L.R. BELDING, VICE-PRESIDENT



My Commission Expires:

May 12, 1985

*Juanita Dick*  
 NOTARY PUBLIC

RECEIVED  
 STATE CORPORATION COMMISSION

DEC 27 1983

CONSERVATION DIVISION  
 Wichita, Kansas