

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 2/89

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-185-22,606-0000 (of this well).

(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR Hellar Drilling Co., Inc. OPERATOR'S LICENSE NO. 5015

ADDRESS 125 N. Market, Suite 1422, Wichita, KS 67202 PHONE # (316) 267-2845

LEASE (FARM) Shepherd-Heter WELL NO. 1 WELL LOCATION SE SE SE COUNTY Stafford

SEC. 15 TWP. 22S RGE. 11 (~~EXX~~(W) TOTAL DEPTH 3644' PLUG BACK TD _____

Check One:

OIL WELL _____ GAS WELL _____ D & A X SWD or INJ WELL _____ DOCKET NO. _____

SURFACE CASING SIZE 8 5/8" SET AT 261' CEMENTED WITH 210 SACKS

CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

PERFORATED AT _____

CONDITION OF WELL: GOOD X POOR _____ CASING LEAK _____ JUNK IN HOLE _____

PROPOSED METHOD OF PLUGGING Circulate heavy mud in hole. 1st plug at 3600'-40 sx. 2nd

plug at 500'-40 sx. 3rd plug at 280'-40 sx. 4th plug at 40'-10 sx. Rathole-15 sx. Water

well-15 sx. All cement 60/40 pozmix, 6% gel.

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? No IS ACO-1 FILED? No

(If not explain.) Sent to operator for completion

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN at 11:30 p.m. on 10-03-89 11-2-89

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE
RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

William Craig, Sr. PHONE # (913) 674-2876

ADDRESS Box 297, Hill City, KS 67642

PLUGGING CONTRACTOR Abercrombie Drilling, Inc. LICENSE NO. 5422

ADDRESS 150 N. Main, Suite 801, Wichita, KS 67202 PHONE # (316) 262-1841

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

SIGNED:

Jack K. Wharton
(Operator or Agent)

DATE:

November 1, 1989

RECEIVED
STATE CORPORATION COMMISSION
NOV - 2 1989
CONSERVATION DIVISION
Wichita, Kansas