

State of Kansas



15-083-20025-0000

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION
NOV 9 1967

11-9-67
CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Pfannenstiel of Leben Drlg. Inc. has this

date requested permission to plug the following described well:

Mr. Pfannenstiel guarantees payment of the plugging fee.

Operator's full Name: Leben Drilling Inc.

Complete Address: 815 Wichita, Plaza, Wichita, Kansas

Lease Name: Springer "A" Well No. 1

Location: 150' S C SE SE Sec. 24 Twp. 22 Rge. 24 (W)

County Hodgeman Total Depth 4620' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Pfannenstiel was instructed to plug the well as follows:

8 5/8" to 519' circulated w/ cement. Mud 4620' to 900'

Spotted 100 sacks cement 900' to 550' Mud 550' to 450'

Spotted 35 sacks cement 450' to 350' Mud 350' to 40'

Plug, Hulls & 10 sacks cement 40' to 0'

Very truly yours,

Edmund J. Evers
Conservation Division Agent