

State of Kansas



## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202  
RECEIVED  
STATE CORPORATION COMMISSIONNOV 30 1970  
CONSERVATION DIVISION  
Wichita, KansasVERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Freeman of Garvey Drlg. Co. Inc. has this  
date requested permission to plug the following described well:Mr. Freeman guarantees payment of the plugging fee.Operator's full Name: Petroleum Inc.Complete Address: 300 W Douglas Wichita, KsLease Name: Deppenbusch K Well No. 1Location: NW/SW/NE Sec. 25 Twp. 30S Rge. 9 (E)(W) WCounty: Kingman Total Depth 4354 Oil Well     Gas Well      Input Well      SWD Well      D & A X Lost Hole     Mr. Freeman was instructed to plug the well as follows:257 ft of 8 5/8 surface pipe cemented with 200 sacks. Fill  
hole to 250 ft, 1/2 sack hulls, plug, 25 sacks cement. Mud to  
40 ft, 1/2 sack hulls, plug, 10 sacks cement to surface.2 sacks cement in rat hole. 2 sacks cement in mouse hole.

Very truly yours,

  
Conservation Division Agent