

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

MAY 1 1963
 5-1-63
 CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Deacon of Forbes Casing Pulling has this

date requested permission to plug the following described well:

Mr. Deacon guarantees payment of the plugging fee.Operator's full Name: Pickrell Drilling Co.Complete Address: 705 4th National Bank Bldg., Wichita, Ks.Lease Name: Scarth Well No. # 1Location: SE SE NW Sec. 33 Twp. 30 Rge. 9 (E) (W) WCounty Kingman Total Depth 4429 Oil Well Gas Well Input Well SWD Well D & A X Lost Hole Mr. Deacon was instructed to plug the well as follows:

232' of 8 5/8" surface pipe, cement circulated. 4428' of
4 1/2" long string, cemented with ¹¹⁵ 150 sacks. Plugged back to
4398'. Perforated from 4351' to 61". Sand to 4340', cement
with 3 sacks. Fill hole to 200', 16' rock bridge, cement
with 20 sacks. Fill hole with mud to 40', 10' rock bridge,
cement with 10 sacks to base cellar.

Very truly yours,

Archie Elving
 Conservation Division Agent