

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
OCT 23 1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Kuhn of Graves Drlg Co has this

date requested permission to plug the following described well:

Mr. Kuhn guarantees payment of the plugging fee.

Operator's full Name: Ablah-Bradley

Complete Address: Box 800 Wichita, KS

Lease Name: Simon Well No. 1

Location: C NE/NE Sec. 2 Twp. 30S Rge. 10 (E)(W)W

County: Kingman Total Depth 2530 Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Kuhn was instructed to plug the well as follows:

217 ft 8 5/8 surface cemented with 250 sacks. Fill hole

to 200 ft, plug, 1/2 sack hulls, 25 sacks cement. Mud to

40 ft, plug, 1/2 sack hulls, 10 sacks cement to surface.

2 sacks cement in rat hole.

Very truly yours,

Russell Bibeart
Conservation Division Agent