

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUN 26 1980

06-26-80

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 009-03088-0000 (of this well)

Operator's Full Name Hinkle Oil Co.

Complete Address 1016 Union Center Bldg., Wichita, Kansas 67202

Lease Name Willenberg Well No. 4

Location SW NE NW Sec. 27 Twp. 16 Rge. 17 (W)

County Barton Total Depth 3372'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Kelso Casing Pulling

Address Box 176 Chase, Kansas 67524 License No. 683

Operation Completed: Hour 12:30 PM Day 24 Month 6 Year 1980

The above well was plugged as follows:

Squeezed thru 10 3/4" Surface casing and 5 1/2" casing with
2 sx hulls, 50 sx cement, 3 sx hulls, 30 sx mud gel, 1 sx
hulls, and 150 sx cement. Max. pres. 600#. Shut in pres. 200#
No casing recovery.

Squeezed from 2176' to 2207' with 200 sx cement.

3368' of 5 1/2" casing cemented with 100 sx cement.

88' of 10 3/4" surface casing cement circ.

I hereby certify that the above well was plugged as herein stated.

Signed: *Dwaine Rankin*
Well Plugging Supervisor