

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
FEB 6 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Addis Oil Operations

Complete Address 5307 East Central, Wichita, Kansas 67208

Lease Name Porteous Well No. 2

Location CEL SW Sec. 31 Twp. 2 2 Rge. (E) (W) 17

County Pawnee Total Depth 4340'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Knight Casing Pulling Co., Inc.

Address Box 405 Chase, Kansas 67524 License No. 436

Operation Completed: Hour 2 P Day 2 Month 2 Year 1974

The above well was plugged as follows:

Total Depth 4340' 8 5/8 csg set at 270' cwc 225 sk.

5 1/2 csg set at 4339' cw 150 sk cem.

Filled 5 1/2 csg W/sd (4260-4340) dumped 4 sk cmt W/dump bailer. (4230-4260)

Cutoff and recovered 3000' of 5 1/2 csg.

~~5 1/2 csg set at 4339' cw 150 sk cem.~~

Pumped down 8 5/8 csg with 20 sk gel & water W/300 lbs hulls -released 8 5/8 plug

and pumped 100 sk 50-50 poz 6% gel.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo F. Massey
Well Plugging Supervisor

INVOICED

DATE 2/8/74

INV. NO. 85.31-W