

KANSAS

## STATE CORPORATION COMMISSION

## CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

RECEIVED  
STATE CORPORATION COMMISSION

SEP 9 1974

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Little George Oil Co.  
Complete Address 225 Sutton Place Wichita Ks.  
Lease Name Jordan Well No. 2  
Location NE-NW-SW Sec. 32 Twp. 22 Rge. 17 (W)  
County Pawnee Total Depth 4265  
Abandoned Oil Well X Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_  
Other well as hereafter indicated \_\_\_\_\_  
Plugging Contractor Kathol Petroleum Inc.  
Address 900 Sutton Place Wichita Ks. License No. 661  
Operation Completed: Hour 12:45 pm Day 4 Month 9 Year 1974

The above well was plugged as follows:

Elev. 2070 8 5/8" - 265" cwc 225 sacks  
5 1/2" - 4264 cwc 175 sacks - Recovered 2700'  
Perf. 4217-22 sand to 4200 5' 4 Sacks Cement.  
Pumped down 8 5/8"  
2 sacks Hulls - 20 sacks Gel - 1 sack Hulls.  
Released Wooden Plug - 100 sacks Common Cement.  
Sun oil well cementing Inc. pump truck.

I hereby certify that the above well was plugged as herein stated.

Signed: Dale H. Bartholomew  
Well Plugging Supervisor

INVOICED

DATE 9/10/74  
INV. NO. 9853-W