

KANSAS

Form CP-3
Rev. 6-1-68

STATE CORPORATION COMMISSION

15-145-00895-0000

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
MAR 18 1974
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Addis Oil Operations

Complete Address 5307 East Central Wichita, Kansas 67208

Lease Name Jordaan Well No. 1

Location NW NW SW Sec. 32 Twp. 22 Rge. (E) (W) 17

County Pawnee Total Depth 4303'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Knight Casing Pulling

Address Box 405 Chase, Kansas 67524 License No.

Operation Completed: Hour 2:30 P Day 103 Month 3 Year 1974

The above well was plugged as follows:

Total Depth 4303' 8 5/8 csg set at 217' cwc 200 sk.

5 1/2 csg set at 4300' cw 175 sk cem.

5 1/2 csg perf. (4234-4239)

Filled 5 1/2 csg W/sd (4200-4303) dumped 4 sk omt W/dump bailer. (4170-4200)

Cutoff and recovered 2600' of 5 1/2 csg.

Ran tubing to 250' & pumped 5 sk gel & water.

Pulled tbg to 210' and circulated 100 sk cement to base of cella.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo F. Mursey
Well Plugging Supervisor

INVOICED
DATE 3/18/74
INV. NO. 8767-W