

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JAN 2 1964

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Earl F. Wakefield & G. I. Ross

Complete Address: 515 Union Center Wichita, Kansas

Lease Name Welch Well No. 1

Location SW SW NW Sec. 32 Twp. 22 Rge. 17 (E) (W) 17

County Pawnee Total Depth 4280

Abandoned Oil Well x Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Barnes & Sons

Address: Russell, Kans License No. 8

Operation Completed: Hour 3PM Day 28 Month 12 Year 63

The Above well was plugged as follows:

10" 281' circulated with cement - 5 1/2" 4276' with 125 sax cement -
Perf at 4206'

Filled with sand to 4190', set 5 sax cement with dump bailer - pumped
40 sax gel & 20 sax weight mud in 10" to 5 1/2" annulus to kill water
flow - pulled 3185' 5 1/2" - pumped 20 more sax gel - pumped wiper plug
followed by 125 sax cement - cement to 0'.

Mudding and cementing by Halliburton Co.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 1/3/64
INV. NO. 8399-W

Signed: *Edwin Letty*
Well Plugging Supervisor