

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

SEP 30 1974

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Little George Oil Co.
Complete Address 225 Sutton Place Wichita Ks.
Lease Name Welch "B" Well No. 3
Location S/2 S/2 NW Sec. 32 Twp. 22 Rge. 17 (X) (W)
County Pawnee Total Depth 4262
Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Kathol Pet. Inc.

Address 900 Sutton Place Wichita Ks. License No. 661

Operation Completed: Hour 8:30 PM Day 26 Month 9 Year 1974

The above well was plugged as follows:

K.B. Elev. 2074 - 8 5/8" @ 242' c/w 225 sacks.
5 1/2" @ 4261' c/w 125 sacks - Recovered 2634'
Perf. 4170-71 sanded back to 4100' & 4 sacks cement.
Pumped down 8 5/8" - 2 sacks Hulls - 20 sacks Gel
1 sack Hulls Released wooden plug.
100 sacks cement 50/50 portmix 6% Gel.
500 cementing pump Truck.
500# pressure.

I hereby certify that the above well was plugged as herein stated.

Signed: Walter Batthazor
Well Plugging Supervisor

INVOICED

DATE 10/1/74
INV. NO. 9980-W